


34-21-24W
C SW SE

34-21-24W
KANSAS



GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

API #15-083-20, 272

EVERTON #1
C SW SE
Section 34-21S-24W
Hodgeman County, Kansas

Commenced: November 29, 1972
Completed: December 10, 1972

OPERATOR: OASIS PETROLEUM, INC.

:290T 001

4151	Y1AN
5000	HEEB
1104	LKC
1054	SH STARK
3424	SC FT
0504	CONG
0404	MISS
0004	MISS DOL
2014	MISS DOL

Depth From To	Formation	Remarks
0 60	Surface clay and sand	Ran 14 jts of used 28#
60 545	Shale-sand	double jts of 8 5/8" csg
545 795	Shale	set @ 607' cemented w/300 sks
795 1195	Shale-redbed	common, 3% CC, 2% G41
1195 1392	Sand	P.D. @ 5 AM Nov. 30, 1972
1392 1620	Shale-sand	Cement Circ.
1620 1718	Shale-shells	
1718 1760	Anhydrite	
1760 2405	Shale-Lime	
2405 2545	Lime-Shale	
2545 2622	Lime	
2622 2775	Shale-lime	
2775 3860	Lime-shale	
3860 3968	Shale-lime	
3968 4649	Lime	
4649 709	Core	
4709 4725	Lime	
4725 TD		



LOG TOPS:

ANHY	1714
HEEB	3967
LKC	4011
STARK SH	4291
FT SC	4548
CONG	4620
MISS	4646
MISS DOL	4666

Ran 152 jts of used 5 1/2" csg.
set @ 4724' cemented w/150 sks
of Howcolite - 100 sks 50-50
Posmix - Plug stop @223
Displaced cement out, waited on
cement and set 2 hr. Pressured
up to 1750 lbs. Released rig
@ 1 PM Dec. 10, 1972

Log for t 1714 & 4725 SW SE, Section 34-21S-24W, Hodgeman County, Kansas, to the best of my knowledge and belief.

James S. Sutton, Jr.
James S. Sutton, Jr.

STATE OF KANSAS)
COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County