

State Geological Survey KANSAS DRILLERS LOG

IMPORTANT
Kans. Geo. Survey request
samples on this well.

API No. 15 — 083 — 20,372
County Number

Operator

Oasis Petroleum, Inc. % Continental Oil Co.

Address 3535 NW 58th Street Oklahoma City, Oklahoma

Well No.

#4

Lease Name

Everton

Footage Location

1980 feet from ~~XXX~~ (S) line 1980 feet from (E) ~~XXX~~ line

Principal Contractor

Slawson Drilling Co.

Geologist

Jerry Jespersen

Spud Date

5-24-74

Total Depth

4715'

P.B.T.D.

4622'

Date Completed

D & A 6-12-74


Oil Purchaser

S. 34 T. 21 R. 24 E W

Loc. 1980 FSL 1980 FEL

County Hodgeman

640 Acres
N



Locate well correctly

Elev.: Gr. 2428'

DF KB 2433'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/2	8 5/8	20 & 23	675	Class H	375	2% gel & 3% Ca.Cl.
Production	7 7/8	5 1/2	15 & 17	4710	Litewate	75	3/4% CFR
					Class H	75	5% KCL, 3/4% CFR-2

LINER RECORD

No

Top, ft.	Bottom, ft.	Sacks cement
----------	-------------	--------------

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	jets	4646-50, 4654-58'

TUBING RECORD

Size	Setting depth	Packer set at
------	---------------	---------------

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
250 gals. MOD 303 acid	4646-58'
1000 gals MOD 202 15% acid	4646-58'

INITIAL PRODUCTION

Dry & abandoned

Date of first production

Producing method (flowing, pumping, gas lift, etc.)

RATE OF PRODUCTION
PER 24 HOURS

Oil

bbls.

Gas

MCF

Water

Gas-oil ratio

bbls.

CFPB

Disposition of gas (vented, used on lease or sold)

Producing interval(s)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Oasis Petroleum, Inc.		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. 4	Lease Name Everton	Dry hole
S <u>34</u> T <u>21</u> S <u>R 24</u> XX W		

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Surface soil & sh	0	1542	Heebner	3948
Lime	1542	2875	Lan. KC	3998
Lime & sh	2875	3830	Starks	4247
Lime	3830	4715	Base LKC	4386
TD		4715	Pawnee	4477
			Ft. Scott	4539
			Cherokee	4562
			Congl.	4611
			Miss.	4646
Mississippi perms. 4646-58'				
Swabbed 33 BW & no oil in 5 hrs.				
Set CIBP at 4630' & spotted cement				
plug 4630-4622'. Will P & A later.				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received



Stan Williams

Signature

Production Engineer

Title

June 18, 1974

Date