

State Geological Survey  
WICHITA BRANCH  
KANSAS DRILLERS LOG

**IMPORTANT**  
Kans. Geo. Survey request  
samples on this well.

API No. 15 — 083 — 20,373  
County Number

Operator

Oasis Petroleum, Inc. % Continental Oil Co.

Address 3535 NW 58th Street Oklahoma City, Oklahoma

Well No.

#5

Lease Name

Everton

Footage Location

660 feet from (N) ~~75~~ line 660 feet from (E) (W) line

Principal Contractor

Slawson Drilling Co.

Geologist

Jerry Jespersen

Spud Date

6-3-74

Total Depth

4700

P.B.T.D.

0

Date Completed

P & A 6-12-74

Oil Purchaser


-----

S. 34 T. 21 R. 24 <sup>E</sup>W

Loc. 660 FNL 660 FEL

County Hodgeman

640 Acres  
N



Elev.: Gr. 2407

DF. KB 2412'

**CASING RECORD**

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	24	687	Class H	225	2% gel., 3% Ca.Cl.
					Class H	150	3% gel.

**LINER RECORD**

None

Top, ft.	Bottom, ft.	Sacks cement

**PERFORATION RECORD**

None

Shots per ft.	Size & type	Depth interval

**TUBING RECORD**

None

Size	Setting depth	Packer set at

**ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD**

None

Amount and kind of material used	Depth interval treated

**INITIAL PRODUCTION**

Dry Hole

Date of first production Producing method (flowing, pumping, gas lift, etc.)

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	bbls.	MCF	bbls.	CFPB

Disposition of gas (vented, used on lease or sold) Producing interval(s)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. 5	Lease Name Everton	Dry Hole
S 34 T 21S R 24 W		


### WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Surface soil & shale	0	1800	Heebner	3942
Lm & sh	1800	2630	Lan. KC	3992
Lm	2630	2850	Starks	4278
Sh & lm	2850	4715	Pawnee	4461
TD		4715	Ft. Scott	4529
			Cherokee	4552
			Conglomerate	4601
			Miss.	4634
<p>DST No. 1, 4611-4642', rec 10' of mud w/a few specks of oil. IF 30", ISI 30", FF 30" FSI 60". Open tool w/weak blow. Died in 15 min. IHH 2363; IFP 36; ISIP 107; FFP 36; FSIP 98; FHH 2327.</p> <p>Conditioned hole w/heavy mud. Spotted 80 sx cement plug 600-700'. Set 15 sx cement plug 45' to surface. Cut off surface pipe 3' below ground level &amp; welded on identifying steel cap. P &amp; A 6-12-74</p>				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.



*Stan Williams*  
Signature

Production Engineer

Title

June 17, 1974

Date