

State Geological Survey
WICHITA, BRANCH
KANSAS DRILLERS LOG

15-083-20514

API No. 15 — 083 — 20,514
County Number

Operator

Icer Addis

Address

P. O. Box 8038, Wichita, Kansas 67202

Well No.

#1

Lease Name

Hoss

Footage Location

feet from (N) (S) line

feet from (E) (W) line

Principal Contractor

Strata Drilling Company

Geologist

Dick Foley

Spud Date

February 2, 1977

Total Depth

4488'

P.B.T.D.

Date Completed

February 11, 1977

Oil Purchaser


D & A

S. 1 T. 21S R. 25W E W

Loc. C NW SW

County Hodgeman

640 Acres
N



Locate well correctly

Elev.: Gr.

DF KB 2,337'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Casing	12 $\frac{1}{4}$ "	8-5/8"		286'	common	180	2% gel, 3% C.C.

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
DRY HOLE					
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	bbls.	MCF	bbls.	CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator ICER ADDIS		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:	
Well No. 1	Lease Name HOSS	DRY HOLE	
S <u>1</u> T <u>21</u> R <u>25</u> [■] W			
WELL LOG		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.			
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME
Anhydrite 1	1,592		Great Guns:
Heebner	3,772		Gamma-Neutron-
Toronto	3,789		Guard-Caliper
Lansing	3,814		4,489
Base Kansas City	4,165		4,488
Marmaton	4,208		4,484
Pawnee	4,296		4,477 Resp.
Fort Scott	4,346		
Cherokee	4,374		
Conglomerate Chert	4,432		
Mississippi	4,452		
Rotary Total Depth	4,488		
DST #1: Open 60" (30-30-30-30) Weak 30" blow; recovered 10' mud w/few specks oil. ISIP 85#, FSIP 63#, IFP 10-10#, FFP 21-21#.	4,458	4,470	
DST #2: Open 60" (30-30-30-30) Slide tool 8 ft. Recovered 150' mud. No show. ISIP 1357#, FSIP 1357#, IFP 74-74#, FFP 96-96# Low Structural Position and Negative Drill Stem Tests results.	4,463	4,480	
Plugged and Abandoned			
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
Date Received	 Icer Addis Owner-Operator March 18, 1977 Date		

1-21-25W

D R I L L E R S L O G

#1 Hoss

CASING RECORD:
280.90' of used
8-5/8" casing

COMPANY: Icer Addis
CONTRACTOR: Strata Drilling Company

DESCRIPTION: C NW SW
Section 1-21S-25W
Hodgeman County, Kansas

TOTAL DEPTH:
4488'

COMMENCED: February 2, 1977
COMPLETED: February 11, 1977

D & A

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface soil and shale	0	300	Ran 280.90' used 8-5/8" surface casing, set and cemented @ 286' with 180 sacks common cement, 2% gel, 3% C.C., cement circulated. Plug down 11:30 P.M., February 2, 1977.
Shale	300	1594	
Anhydrite	1594	1620	
Shale	1620	2430	
Shale and Lime	2430	4280	
Lime	4280	4355	Ran 2 Drill Stem Tests
Lime and Shale	4355	4460	
Mississippi	4460	4488	

ROTARY TOTAL DEPTH: 4488'

Ran 1 electric log.

D. & A.

Hole plugged as follows: plugged at 900' with 50 sacks of 50/50 pozmix, 6% gel; plugged at 300' with 25 sacks of 50/50 pozmix, 6% gel; plugged at 40' with hulls and 15 sacks 50/50 pozmix, 6% gel; plugged mousehole and rathole with 5 sacks 50/50 pozmix, 6% gel, each. Plug down at 5:10 A.M., February 11, 1977.

STATE OF KANSAS)
) ss
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of