

API No. 15 — 083 — 20,360
County Number

Operator

O. A. Sutton

Address 800 Sutton Place

Wichita, Kansas 67202

Well No.

#1

Lease Name

Sinclair

Footage Location

660 feet from (N) (S) line

660 feet from (E) (W) line

Principal Contractor

Gabbert-Jones, Inc.

Geologist

Stanton Cox

Spud Date

August 16, 1974

Total Depth

4470'

P.B.T.D.

Date Completed

August 29, 1974

Oil Purchaser


S. 9 T. 21 R. 25 E W

Loc. SW SW

County Hodgeman

640 Acres

N



Locate well correctly

Elev.: Gr. 2352'

DF 2354' KB 2357'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface		8-5/8"	28#	411'	common	250	2% gel, 3% 33

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated


INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS		Oil	Gas	Water	Gas-oil ratio
		bbls.	MCF	bbls.	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator O. A. Sutton		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: Dry Hole		
Well No. 1	Lease Name Sinclair			
S <u>9</u> T <u>21</u> SR <u>25</u> ^{EX} _W				
WELL LOG		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.		
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.				
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1, 4147-4200', open 1 hour, weak blow 25 min. & died; rec. 30' mud; IBHP 1165# 45 min., FBHP 1102# 45 min.; FP 40-54#. DST #2, 4314-4355', open 1 hour, weak blow 10 min., rec. 5' mud with few specks oil; IBHP 54# 30 min., FBHP 42# 30 min.; FP 42-42#. DST #3, 4346-4380', open 90 min., rec. 75' slightly oil-cut mud; IBHP 836# 45 min., FBHP 705# 60 min. (final BHP malfunctioned); FP 82-112#. DST #4, 4382-4390', open 1 hour, weak blow 5 min. & died; rec. 10' mud with few specks oil; IBHP 95# 30 min., FBHP 63# 30 min.; FP 20-42#. DST #5, 4390-4405', open 45 min., weak blow 10 min. & died; rec. 5' mud with few specks oil; IBHP 40# 30 min., FBHP 40# 30 min.; FP 40-40#.			Log tops: Anhydrite 1578 (plus 779) Base Anhydrite 1616 (plus 741) Heebner 3701 (-1344) Toronto 3718 (-1361) Lansing 3741 (-1384) Stark 4012 (-1655) BKC 4116 (-1759) Marmaton 4144 (-1787) Pawnee 4220 (-1863) Ft. Scott 4264 (-1907) Cherokee 4291 (-1934) Mississippian 4376 (-2019) Osage 4426 (-2069) Log TD 4474 (-2117)	

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.





Signature

Exploration Manager

Title

October 24, 1974

Date