

WICHITA, BRANCH

KANSAS DRILLERS LOG

IMPORTANT
 Kans. Geo. Survey request
 samples on this well.

 API No. 15 — 083 — 20,452
 County Number

Operator

Raymond Oil Company, Inc.

Address

Suite 800, 200 West Douglas Wichita, Kansas 67202

Well No.

#1

Lease Name

Vieux

Footage Location

710 feet from (N) ☒ line 660 feet from ☒ (W) line

Principal Contractor

Rains & Williamson

Geologist

Chas. B. Spradlin

Spud Date

January 2, 1976

Total Depth

4445'

P.B.T.D.

Date Completed


January 14, 1976

Oil Purchaser

S. 14 T. 21 R. 25 ^KW

Loc. NW NE

County Hodgeman

640 Acres
N

Locate well correctly

Elev.: Gr. 2300

DF 2303 KB 2305

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4	8-5/8		265	Common	200	2% gel, 3% cc
Production		5-1/2	15-1/2	4438	60/40 Pos.	150	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
				Open hole	4438-45

TUBING RECORD

Size	Setting depth	Packer set at
2-1/2	4438	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
5,000 gal., 15% NE acid	4438-45

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)		
RATE OF PRODUCTION PER 24 HOURS	Oil bbls.	Gas MCF	Water bbls.	Gas-oil ratio CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval (s)	

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

State Geological Survey

WELL LOG

WICHITA, BRANCH

COMPANY RAYMOND OIL CO., INC.

SEC. 14 T. 21S R. 25W

LOC. NW/4 NE/4

FARM VIEUX

NO. 1


RIG. NO. 7

TOTAL DEPTH 4445'

COMM. 1-2-76

COMP. 1-15-76

COUNTY HODGEMAN
KANSAS



CONTRACTOR RAINS & WILLIAMSON OIL CO., INC.

CASINO

20 10
15 8 -5/8" @ 265' w/200 sxs common.
12 6 2% gel. 3% cc.
13 5 1/2" @ 4438' w/150 sxs. 60/40 pos.

ELEVATION 2300 GL

PRODUCTION OIL

FIGURES INDICATE BOTTOM OF FORMATIONS

SURFACE CLAY & SHALE	275
SHALE & SAND	1035
SAND	1380
SHALE	1547
ANHYDRITE	1586
SHALE	1935
SHALE & LIME	2820
LIME & SHALE	3003
SHALE & LIME	3095
LIME & SHALE	3320
SHALE & LIME	3420
LIME & SHALE	3965
LIME	4445
<u>ROTARY TOTAL DEPTH</u>	<u>4445</u>

RECEIVED
STATE GEOLOGICAL SURVEY

JAN 19 1976

CHIEF ENGINEER
JAN 19 1976