


KANSAS DRILLERS LOG

State Geological Survey
WICHITA, BRANCHAPI No. 15 — 083 — 20,296
County NumberS. 14 T. 21 R. 25 WLoc. C. SW SECounty Hodgeman640 Acres
N

Locate well correctly

Elev.: Gr. 2364'DF 2367' KB 2369'

Operator

Petroleum, Inc.

Address

300 West Douglas, Wichita, Kansas

Well No.

2

Lease Name

VIEUX 'D'

Footage Location

660 feet from (S) line 1980 feet from (E) line

Principal Contractor

Strata Drilling, Inc.

Geologist

Victor F. Reiserer

Spud Date

April 5, 1973

Total Depth

RTD 4503'

P.B.T.D.

Date Completed

May 15, 1973

Oil Purchaser

None

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	20#	404'	Common	225	2% Gel, 3% CC
Production	7-7/8"	5-1/2"	11#	4502'	50-50 Poz. 3/4 of 1% CFR2	75	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	DP	4484-90'
TUBING RECORD			4	DP	4480-86'
Size	Setting depth	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
500 gal. MOD 202	Open Hole 4502-4511'
1750 Gal. MOD 202 w/8 gal 13N-5	4480-90'
5000 gal. CRA	Down casing

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
None					
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	bbls.	MCF	bbls.	CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Petroleum, Inc.		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: Dry hole, No Commerical
Well No. 2	Lease Name VIEUX 'D'	Zone, Plugged & Abandoned
S <u>14</u> T <u>21</u> R <u>25</u> W C. SW SE		8/20/73. Pulled Prod. Casing.

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1: 4476-90: 30-30-30-60; Weak steady blow, increasing on the 2F; 210' gas in the pipe, 10' free oil, 200' muddy gas cut oil; 1FP 10#-40#, 1BHP 1136#, 2FP 71#-91#, 2BHP 1087#			Dresser Atlas	GR-N-LL Tops:
DST #2: 4490-97: 30-30-30-30; Weak blow, died on the 2F; 1' free oil, 19' slightly oil cut mud, 1FP 2#-2#, 1BHP 1090#, 2FP 2#-2#, 2BHP 990#			Heebner	3794
			Toronto	3808
			Lansing	3839
			Fort Scott	4368
			Mississippi	4463
			LTD	4502
DST #3: 4492-4503: 30-30-30-60; Weak blow; 96' slightly oil cut muddy water; 1FP 10#-30#, 1BHP 1100#, 2FP 40#-50#, 2BHP 1080#				

PETROLEUM, INC. #2 VIEUX "D" 14-21-25W
 300 W. DOUGLAS, WICHITA, KS. C SW SE
 CONTR _____ CTY HODGEMAN
 GEOL VIC REISERER FIELD STAIRETT
 E 2369 KB CM 4/5/73 CARD ISSUED 5/24/73 IP TEMP ABD

API 15-083-20,296

LOG	TOPS	DEPTH	DATUM
HEEB		3794	-1425
TOR		3808	-1439
LKC		3839	-1470
FT SC		4368	-1999
MISS		4463	-2094
LTD		4502	-2133
RTD		4503	-2134
DDTD		4511	-2142

8 5/8" 404/225SX; 5 1/2" 4502/75SX
 DST(1) 4476-90/30-30-30-60, 210' GIP, 10' FO, 200' MGCO, BHP 1136-1087#, FP 10-40# & 71-91#
 DST(2) 4490-97/30-30-30-30, 1' FO, 19' SOCM BHP 1090-990#, FP 2-2# & 2-2#
 DST(3) 4492-4503/30-30-30-60, 96' SOCMW, BHP 1100-1080#, FP 10-30# & 40-50#
 MICT, DD 4511, SWB 3.9BW A500 REC LD SWB 1.17BF 95%WTR/1HR, PF 4480-90 BP @ 4495 SWB 10.43GOPH/6HRS N/W A2000, SWBG LD REC LD SWB 3.29BFPH 63%WTR RE-AC 5000 REC LD AVG 19BFPH 93%WTR

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.



C.H. Dumbler

 Signature
 Office Manager

 Title
 August 22, 1973

 Date