

APR 11 1970

DRILLERS LOG

#1 Grass

CASING RECORD: 283.60' of new 8-5/8" surface casing.

COMPANY: R. V. Lehner

DESCRIPTION: C/AS in Section 15-213-250
Hodgeman County, Kansas

CONTRACTOR: Strata Drilling, Inc.

TOTAL DEPTH: 4460'

COMMENCED: June 14, 1969

ELEVATION: 2317' KB

COMPLETED: June 23, 1969

D. & A.

Dry/miss

FORMATION

FROM

TO

REMARKS

Surface Clay & Rock
Post Rock, Clay, Sand &
Shells
Clay & Shale
Shale
Shale & Red Bed
Anhydrite
Red Bed, Shale & Shells
Shale
Lime & Shale
Lime
Cherty Lime

0
115
308
660
1435
1545
1571
1968
2266
4174
4440
4460

Ran 283.60' of new 8-5/8" surface casing; set and cemented at 283.60' with 155 sacks of regular cement. Plug down at 8:10 P. M. June 14, 1969.

anhydrite 1545
Base 1571

Total Depth 4460'

D. & A.



Plugged hole as follows: plugged at 350' with 30 sacks of cement; plugged at 200' with 30 sacks of cement; plugged at 40' with 10 sacks of cement and 2 sacks in the mouse-hole. Plug down at 10:00 A. M. June 23, 1969.

STATE OF KANSAS)
COUNTY OF BARTON) ss.