

**State Geological Survey
WICHITA, BRANCH**

KANSAS DRILLERS LOG

API No. 15 — 083 — 20,316
County Number

Operator

O. A. Sutton

Address

800 Sutton Place, Wichita, Kansas 67202

Well No.

1

Lease Name

Jackson

Footage Location

660 feet from (N) (S) line

660 feet from (E) (W) line

Principal Contractor

Gabbert-Jones, Inc.

Geologist

Robert M. Euwer
Richard K. Grant &

Spud Date

July 27, 1973

Total Depth

4415'

P.B.T.D.

Date Completed

August 9, 1973


Oil Purchaser

S. 17 T. 21S R. 25 ^{XX}W

Loc. C SW SE

County Hodgeman

640 Acres
N



Locate well correctly

Elev.: Gr.

DF KB 2334

CASING RECORD

Report of all strings set—surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface		8-5/8"	28#	430'	Common	sacks	2% gel, 3% cc

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at


ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS		Oil bbls.	Gas MCF	Water bbls.	Gas-oil ratio CFPB
Disposition of gas (vented, used on lease or sold)				Producing interval (s)	

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator O. A. Sutton		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: Dry Hole	
Well No. 1	Lease Name Jackson		
S <u>17</u> T <u>21</u> S <u>R 25</u> ^W W			
WELL LOG		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.			
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME
Surface-soil-sand-shale	0	430	Log tops:
Shale & sand - Redbed	430	1050	Anhydrite 1526
Sand	1050	1215	Heebner 3652
Shale	1215	1478	Lansing 3694
Shale-Redbed	1478	1915	Stark shale 3970
Shale	1915	2151	BKC 4093
Anhydrite	2151	2191	Pawnee 4190
Shale-shells	2191	2355	Ft. Scott 4226
Shale & lime	2355	2705	Cherokee 4252
Lime & shale	2705-3845		Conglomerate 4302
Lime	3845	4315	Mississippian 4332
Lime	4315	4395	Log TD 4406
Lime & chert	4415		
Lime & chert	4395	4415	
DST #1, 4341-4360', open 30 min., SI 30 min., open 90 min., SI 60 min., weak blow, rec. 10' free oil, 30' muddy oil (30' grindout - 40% oil, 30% mud, 30% water); IFP 23-23#, FFP 23-23#; IBHP 1113# 30 min., FBHP 1160# 60 min. DST #2, 4395-4415', open 2 hours, weak blow increasing to strong, rec. 130' muddy salt water, 310' salt water, NS; IFP 23-95#, FFP 107-203#; IBHP 1314# 30 min., FBHP 1314# 60 min.			
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
	 _____ Signature Exploration Manager _____ Title August 26, 1975 _____ Date		