

KANSAS

WELL COMPLETION REPORT AND
DRILLER'S LOG


IMPORTANT
Kans. Geo. Survey request
samples on this well.

State Geological Survey
WICHITA, BRANCH

S. 17 T. 21 R. 25 W

Loc. C NW SW

County Hodgeman

640 Acres
N

Locate well correctly

Elev.: Gr. 2334

DF 2340 KB 2341

API No. 15 — 083 — 20,812
County Number

Operator

PETX Petr. Corp.

Address

1700 Security Life Bldg. Denver, Colo 80202

Well No.

#1

Lease Name

Sinclair

Footage Location

1980' feet from (N) (S) line 660 feet from (E) (W) line

Principal Contractor

Slawson Drilling Co.

Geologist

Mathew Goolsby

Spud Date

1/9/81

Date Completed

2/27/81

Total Depth

4410'

P.B.T.D.

4396'

Directional Deviation

Oil and/or Gas Purchaser

CASING RECORD

Report of all strings set—surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/2"	8 5/8"	24#	515'	Poz 60/40 Mix	275	2% Gel 3% CaCl
Production	7 7/8"	4 1/2"	10.5#	4409'	Poz 60/40 Mix	150	2% Gel 3% CaCl

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
None					
TUBING RECORD					
Size	Setting depth	Packer set at			
2"	4390'	4347'	2	Casing Jet Charges	4365-4368 4360-4365
			2	Casing Jet Charges	4368-4372 4375-4382

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
600 Gal of 15% MCA acid	All perfs
3000 gals. of 15% MOD 202 Acid	All perfs

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
3/1/81		Pumping			
RATE OF PRODUCTION PER 24 HOURS		Oil	Gas	Water	Gas-oil ratio
10.02		bbls.	-0- MCF	-0- bbls.	----- CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		
None			All perfs		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. #1	Lease Name Sinclair	Oil
S17 T21SR25W ^E _W		


WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Anhydrite	1535'			
Heebner	3674'			
Lansing	3715'			
B/ Kansas City		4097'		
Ft. Scott	4204'			
Cherokee	4271'			
Conglomerate	4325'			
Mississippian	4348'			
TD	4408'			
DST #1 4359-4374', open 15 min., shut-in 30 min., open 60 min., shut-in 120 min., recovered 30' gassy oil cut mud, 90' oil cut mud, 30' mud cut oil. No water. IHP-2242, IFP-26-54, ISIP-1028, FF-62-94#, FSIP-1158#, FH-2242#, BHT-108 degrees Logs - GO Wireline Services DIL w/SP 516-4408 CDL/CNL w/GR-Caliper 2396-4408' WEL 2400-4408' 5-Track 2400-4408'				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	 Harrell Budd Manager of Geology 3/20/81
	Signature Title Date

DRILLERS LOG

OPERATOR: PETX Petroleum Corporation
1616 Glenarm Place
1700 Security Life Building
Denver, Colorado 80202

WELL NAME: Sinclair #1
C NW SW Sec.17-21S-25W
Hodgeman County, Kansas

CONTRACTOR: Slawson Drilling Company, Inc.
200 Douglas Building
Wichita, Kansas 67202

COMMENCED: 1/10/81

COMPLETED: 1/20/81

RTD: 4410'

SURFACE CASING: 8-5/8" set at 515' with 275 sx cement


PRODUCTION CASING: 4-1/2" set at 4409' with 150 sx cement

0' to 517' (12 1/2" Surface Hole)
517' to 1540' Shale
1540' to 1577' Anhydrite
1577' to 2166' Shale
2166' to 2410' Shale & Shells
2410' to 2860' Shale
2860' to 3025' Shale & Lime
3025' to 3189' Lime & Shale
3189' to 3430' Shale & Lime
3430' to 3565' Lime & Shale
3565' to 3700' Shale & Lime
3700' to 4374' Lime
4374' Mississippian
4374' to 4410' Lime (Mississippian)
RTD 4410'

STATE OF KANSAS

COUNTY OF SEDGWICK

I, James C. Remsberg, of the Slawson Drilling Company, Inc.
hereby state the above is an accurate copy of the #1 Sinclair log for
PETX Petroleum Corporation.


James C. Remsberg