

23-21-25W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- HUDSON PETROLEUM CO.
Farm- Lee No. #5

SEC. 23 T. 21 R. 25W
C SE SE

Total Depth. 4530'
Comm. 12-16-63 Comp. 12-28-63
Shot or Treated.
Contractor. Jones-Gebert Oil
Issued. 4-4-64

County Hodgeman
KANSAS



CASING:

Elevation. 2405' KB

8 5/8" 267' cem w/ 200 sx
5 1/2" 4485' cem w/ 75 .sx

Production. 145 BOPD

Figures Indicate Bottom of Formations.

soil & shale	160
shale	260
sandy shale & shells	700
shale	1515
shale & shells	1765
shale	2110
shale	2340
lime & shale	2445
sandy lime w/shale	3130
shale & lime	3625
lime w/chalk	3800
lime & shale	3940
lime w/shale	4030
lime & shale	4117
lime	4200
lime w/shale	4268
lime & shale	4335
lime & shale	4390
lime w/shale	4325
lime & shale	4465
lime & chert	4492
Mississippi Core #1	4499
Core	4520 RTD
Total Depth	

TOPS: SMP

Heebner	3807
Lansing	3859
Base Kansas City	4233
Marmaton	4273
Fort Scott	4390
Mississippi	4481
Mississippi Dolomite	4490