

508 East Murdock,

Wichita, Kansas


23-21-25W

Company- JONES GEBERT OIL
Farm- Lee "A" No. 1

SEC. 23 T.21 R. 25W
C NW SE

Total Depth. 4561'
Comm. 6-8-63 Comp. 6-19-63
Shot or Treated.
Contractor. Jones- Gebert Oil,
Issued. 11-2-63

County HODGEMAN
KANSAS



CASING:

8 5/8" 217' cen w/ 200 sx
5 1/2" 4533' cen w/ 125 sx

Elevation. 2430 KB

Production. 173 BOPD - N W

Figures Indicate Bottom of Formations.

red bed & clay w/ shale	170
hard cement	217
clay & unconsolidated shale	1040
shale	1505
shale & anhydrite	1635
shale	1860
shale w/ lime streaks	2285
shale & lime	2495
lime & shale (Ft. Riley)	2610
lime	2740
lime	2920
lime & shale	3145
shale & lime	3465
lime & shale	3580
shale & lime w/ chalk streaks	3710
shale & chalk w/ lime streaks	3844
lime	3920
lime & shaley lime	4020
lime	4122
lime w/ shaley lime streaks	4227
lime w/ shale streaks	4279
lime	4324
lime w/ shale	4358
lime w/ shale streaks	4398
lime	4464
lime w/ some chert	4508
lime	4530
core #1	4539
core #1	4560
core# 1	4563
RTD	4561
Total Depth	

TOPS: LOG

Anhydrite	1651
Base anhydrite	1690
Heebner	3838
Lansing	3886
Base Kansas City	4260
Cherokee	4439
Mississippi lime	4508
Mississippi Dolomite	4522