

23-21-25W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- HUDSON PETROLEUM
Farm- Lee "A" No. 5

SEC. 23 T. 21 R. 25W
C SW NE

Total Depth. 4555'
Comm. 2-24-64 Comp. 3-7-64
Shot or Treated.
Contractor. Sholom Drlg.
Issued. 5-16-64

County Hodgeman
KANSAS



CASING:

8 5/8" 320' cem w/ 275 sx
4 1/2" 1400' cem w/ 259 sx

Elevation. 2398' KB

Production. DRY

SWPH

Figures Indicate Bottom of Formations.

surface clay	60
shale, shells, sand streaks	725
red bed, shale, shells	982
Gyp & shale	1010
Gyp	1029
shale & shells	1105
sand	1320
shale, shells, red bed	1652
anhydrite	1678
shale & shells	2410
lime & shale	2575
lime	3055
lime & shale	3105
lime	3215
lime & shale	3915
lime	4555
Total Depth	

TOPS: SCOUT

Cedarhills	1110
Heebner	3819
Lansing	3867
Mississippi Lime	4518

Core 4504-20

DST 4519-36

Op 1 1/2 hrs. Rec. 885' water . IBHP 1253-1074

FP 76-382