


Company- PET., INC.
Farm- Lee "C"

No. 1

SEC. 23 T. 21 R. 25W
C SW SW

23-21-25W

County Hodgeman
KANSAS



Total Depth. 4573' (4570)
Comm. 11-30-63 Comp. 12-14-63
Shot or Treated.
Contractor. Garvey Drilling Co.
Issued. 5-9-64

CASING:

8 5/8" 421' cem w/325 sx.
5 1/2" 4558' cem w/100 sx.

Elevation. 2449' RB

Production. 46 BOPD, 48% WTR.

Figures Indicate Bottom of Formations.

surface soil, sand, & shale	70
shale & sand	421
shale	480
redbed & shale	575
shale	825
redbed & shale	1050
Anhydrite	1065
shale & shells	1200
sand	1375
shale	1625
shale & redbed	1680
Anhydrite	1710
shale & shells	1927
shale & lime	2340
lime & shale	2600
lime	2630
lime & shale	2765
lime	2870
lime & shale	3110
lime	3180
lime & shale	3300
shale & lime	3387
lime & shale	3515
shale & lime	3630
lime & shale	3885
shale	3900
lime	3947
Lansing Lime	4010
lime	4233
lime & shale	4535
lime & cherty lime	4559
lime	4570 RTD
lime	4573
Total Depth	
TOPS: LOG	
Blaine	1010
Base Blaine	1060
Anhydrite	1655
Base Anhydrite	1696
Heebner	3850
Lansing	3900
Marmaton	4306
Ft. Scott	4430
Conglomerate	4517
Weakened Mississippi	4530
Mississippi	4534
Mississippi Dolomite	4556