

26-21-25W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 503 East Murdock, Wichita, Kansas

Company- **PETROLEUM, INC.**
 Farm- Wright "J" No. 2

SEC. 26 T. 21 R. 25W
 App. C NW NE

Total Depth. 4610'
 Comm. 2-1-64 Comp. 2-12-64
 Shot or Treated.
 Contractor. Garvey Drlg. Co.
 Issued. 4-10-65

County Hodgeman
 KANSAS



CASING:

Elevation. 2416' D.F.

8 5/8" 400' w/290 sx cem.
 5 1/2" 4608' w/75 sx cem.

Production. Pmp. 111 BOPD-NW

Figures Indicate Bottom of Formations.

surface clay, sand	55
shale	400
shale w/sand, strks	
red bed	985
Anhydrite	1030
shale	1150
sand	1375
red bed, shale	1628
Anhydrite(second)	1655
shale, Gyp strks	1820
shale, lime strks	2460
lime	2680
lime, shale	2800
lime	2930
lime, shale	3240
shale w/lime strks	3542
shale, lime	3668
lime, shale w/chalky strks	
	3817
shale, lime	3890
lime	4543
lime, chert	4610
Rotary Total Depth	

TOPS: SCOUT	
Shhydrite	1625
Heebner	3816
Toronto	3834
Lansing	3866
B/Kansas City	4248
Marmaton	4276
Fort Scott	4403
Cherokee	4428
Conglomerate	4491
Mississippi lime	4498
Mississippi Dolomite	4516
Mississippi Osage	4569