

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock,

Wichita, Kansas


26-21-25W

Company- PETROELUM, INC.
Farm- Wright "J" No. 3

SEC. 26 T. 21 R. 25W
C NE NE

Total Depth. 4581'
Comm. 2-13-64 Comp. 2-25-64
Shot or Treated.
Contractor. Garvey Drilg. Co.
Issued. 4-10-65

County Hodgeman
KANSAS



Elevation. 2383' D.F.

8 5/8" 400' w/275 sx cem.
5 1/2" 4579' w/75 sx cem

Production. Pmp. 81 BOPD, 41% wtr.

Figures Indicate Bottom of Formations.

surface clay, sand	40
sdv shale	150
shale	400
sdv shale	507
shale, sand	847
red bed	930
Anhydrite	975
shale	1080
sand, shale	1340
red bed	1603
Anhydrite #2	1615
shale w/lime strks	2100
shale, lime	2275
lime w/shale strks	2355
lime, shale	2525
lime	2850
shale w/lime	3000
shale, lime w/chalky strkks	3040
lime, shale	3135
lime, shale w/chalk strks	3350
shale w/lime strks	3610
lime, shale w/chalk strks	3720
lime, shale	3930
lime	4440
lime, shale	4482
lime	4581
Rotary Total Depth	

TOPS: SCOUT
Heebner 3798
Toronto 3814
Lansing 3846
B/Kansas City 4224
Fort Scott 4375
* Cherokee shale 4405
* Conglomerate 4459
Mississippi lime 4477
Mississippi Dolomite 4489

* Sample tops/