

State Geological Survey
WICHITA, BRANCH
KANSAS DRILLERS LOG

IMPORTANT
Kans. Geo. Survey request
samples on this well.

API No. 15 — 083 — 20,477
County Number

Operator

Dunne-Gardner & Sotex Co., Inc.

Address

Suite 250, 200 West Douglas Wichita, Kansas 67202

Well No.

#1

Lease Name

Clark

Footage Location

660

feet from (N) (S) line

660

feet from (E) (W) line

Principal Contractor

Dunne-Gardner Petroleum Inc

Geologist

Don F Moore

Spud Date

7-26-76

Total Depth

4567

P.B.T.D.

Date Completed

8-10-76


Oil Purchaser

S. 27 T. 21 R. 25 W

Loc. SW NW

County Hodgeman

640 Acres
N



Locate well correctly

Elev.: Gr. 2429

DF 2436 KB 2438

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4	8-5/8	20#	329'	Common	250	2% gel

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at


ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	bbis.	MCF	bbis.	CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Dunne-Gardner Petroleum, Inc.		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWPW, ETC.: Dry Hole	
Well No. 1	Lease Name Clark		
S 27 T 21 R 25 W ^E _W			
WELL LOG Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME
Shale and sand	0	327	Heebner
Shale and shells	327	985	Toronto
Shale	985	1145	Lansing
Sand	1145	1345	BKC
Shale and red bed	1345	1658	Marmaton
Anhydrite	1658	1697	Ft. Scott
Shale and shells	1697	2376	Cherokee
Lime and shale	2376	3220	Congl.
Lime	3220	3405	Miss. Dol.
Lime and shale	3405	3938	
Lime	3938	4030	
Lime and shale	4030	4130	
Lime	4130	4567	
DST #1, 4500-4535, 45-45-45-45, recovered 60' SO&GCM, 60' OCM BHP 173-151, IFP 54-76, FFP 97-97			Petro-Log GR N G Cal
DST #2, 4535-4560, 45-45-45-45, recovered 110' thin oil spotted mud. BHP 1270-1238, IFP 32-43, FFP 54-65			
DST #3, 4560-4567, 45-45-45-45, recovered 1090' sulfur water. BHP 1248-1227, IFP 32-303, FFP 335-498			
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
Date Received	 Signature Vice-President Title September 8, 1976 Date		