

15-083-20570

IMPORTANT
Kans. Geo. Survey request
samples on this well.

KANSAS DRILLERS LOG

API No. 15 — 083 — 20,570
County Number

Operator
J. A. Allison

Address 300 West Douglas, Suite 305 Wichita, Kansas 67202

Well No. #1 Lease Name Evans

Footage Location
feet from (N) (S) line 660 feet from (E) (W) line 660

Principal Contractor DNB DRILLING, INC. Geologist Kenneth W. Johnson

Spud Date December 23, 1977 Total Depth 4466 P.B.T.D.

Date Completed January 3, 1978 Oil Purchaser

9 8 9 T. 21 R. 26 E W
Loc. C NW SE
County Hodgeman
640 Acres
N
160 160 160 160
Locate well correctly
Elev.: Gr. 2427
DF KB 2432

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs./ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface		8-5/8		282'	Common	175	2% gel 3% cc

LINER RECORD

PERFORATION RECORD

Top, ft. none	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
none	

INITIAL PRODUCTION

Date of first production none	Producing method (flowing, pumping, gas lift, etc.)
RATE OF PRODUCTION PER 24 HOURS	Oil Gas Water Gas-oil ratio
	bbls. MCF bbls. CFPB
Disposition of gas (vented, used on lease or sold)	Producing interval (s)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator J. A. ALLISON		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:	
Well No. 1	Lease Name EVANS	DRY HOLE	
S <u>9</u> T <u>21</u> S <u>R26</u> W ^E _W			
WELL LOG		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.			
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME DEPTH
DST #1-op 45", SI 45; op 30, si 45 Weak blow thru first open period, dead on second open period. Rec 15' mud w/few specks oil. IFP 42-42, ISIP 63#, FFP 42#-42# FSIP 42# Temp. 120 deg.	4417	4428	ELECTRIC LOG TOPS: Heebner 3726 Lansing-K.C. 3771 Base K.C. 4180 Marmaton 4210 Ft. Scott 4217 Cherokee 4343 Mississippi 4430
DST #2-op 30, si 30; op 30, si 30 Weak blow for 25 min. of first open, dead on second open period. Rec. 19' mud w/speck of heavy oil. IFP 42#-42#, ISIP 63# FFP 42#-42#, FSIP 42# Temp. 120 deg.	4420	4431	
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
Date Received	J. A. Allison Signature OPERATOR Title March 31, 1978 Date		

State Geological Survey

WICHITA BRANCH

DRILLERS' LOG

15-083-20570
9-21-26W

J. A. ALLISON
No. 1 Evans
C NW SE Sec. 9-21S-26W
Hodgeman Co., Kansas

Commenced: 12-23-77
Completed: 1-3-78

Surface casing: 273.82' of 8-5/8"
cmt'd w/175 sx common, 2% gel, 3% cc
12-23-77

FORMATION

DEPTH

Surface Hole	0 - 282
Sand & Shale	282 - 600
Shells & Shale	600 - 1126
Sand	1126 - 1375
Shale	1375 - 1477
Shale & Red Bed	1477 - 1640
Anhydrite	1640 - 1674
Shale	1674 - 2035
Shale & Lime	2035 - 2810
Lime & Shale	2810 - 3125
Shale & Lime	3125 - 3340
Lime & Shale	3340 - 4130
Lime	4130 - 4470 RTD

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

Ella Priess

Ella Priess

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 4th day of January, 1978.

Dorothy L. Schmidt

Dorothy L. Schmidt, Notary Public