

State Geological Survey KANSAS DRILLERS LOG

IMPORTANT
Kans. Geo. Survey request
samples on this well.

API No. 15 — 083 — 20,453
County Number

Operator

Patrick Petroleum Corp. & Petroleum Inc.

Address Suite 414, 200 East First Wichita, Kansas 67202

Well No.

#1

Lease Name

Evans

Footage Location

660'

feet from (N) line

1980'

feet from (E) line

Principal Contractor

DNB DRIG. Inc.

Geologist

MIKE MITCHELL

Spud Date

FEB 5, 1976

Total Depth

4452

P.B.T.D.

Date Completed

FEB 12, 1976


Oil Purchaser

S. 9 T. 21 R. 26^R_W

Loc. C NW NE

County Hodgeman

640 Acres
N



Locate well correctly

Elev.: Gr. 2445

DF 2447 KB 2450

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
SURFACE		8 5/8		273'	Common 70% bel, 30% cc.	180 sx.	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
- NONE -	

INITIAL PRODUCTION

Date of first production

NONE

Producing method (flowing, pumping, gas lift, etc.)

RATE OF PRODUCTION
PER 24 HOURS

Oil

bbls.

Gas

MCF

Water

Gas-oil ratio

bbls.

CFPB

Disposition of gas (vented, used on lease or sold)

Producing interval(s)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

PATRICK PETROLEUM CORP. & PETROLEUM INC.

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

Well No.

1

Lease Name

EVANS

DRY HOLE

S 9 T 21 S R 26 E W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.

TOP

BOTTOM

NAME

DEPTH

MISSISSIPPI DOLOMITE -

Lm., H. qv. f.xln sacrosic dolo.

w/ poor - fair ppt. & vuggy &

USFO, NFWOF 10-20% w/STAIN

DST # 1 4442-52 30"-30"-30"-30"

Rec. 130' sl. oc wtr.

660' wtr.

740' TOTAL FLUID

SIP 1308/1296" - 30"

FP 46/230" 265/426"

4445

STILL IN
@ 4452

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.



Michael S. Mitchell

Signature

GEOLOGIST - PATRICK PETROLEUM CORP

Title

MARCH 10, 1976

Date

State Geological Survey
WICHITA, BRANCH

DRILLERS' LOG

15-083-20453 ✓
9-21-26W

PATRICK PETROLEUM CORPORATION

No. 1 Evans

C NW NE, Sec. 9-21S-26W

Hodgeman County, Kansas

Elev: 2450 K.B.

Commenced: 2-5-76

Completed: 2-13-76

Surface Casing: 265' of
8-5/8" cemented w/180 sx
common cement, 2% Gel, 3% cc.
2-5-76

FORMATION

DEPTH

Surface Hole	0 - 273
Shale	273 - 1035
Shale & Sand	1035 - 1070
Blaine Anhydrite	1070 - 1085
Shale, Sand & Red Bed	1085 - 1664
Anhydrite	1664 - 1705
Shale	1705 - 2320
Shale & Lime	2320 - 2520
Lime & Shale	2520 - 3850
Lime	3850 - 4452 RTD

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

James L. Donelson
JAMES L. DONELSON

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 26th day of February 1976.

Ella Priess
Ella Priess, Notary Public



Ella Priess
STATE NOTARY PUBLIC
Sedgwick County, Kansas
My Com. Expires Aug. 25, 1976