

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock,

Wichita, Kansas

14-21-26 W

Company- SUNRAY D X OIL
Farm- Joe Clifton

No. 1

SEC. 14


T. 21

R. 26W

C NE NE

Total Depth. 4585' (4589)
Comm. 12-22-63 Comp. 1-3-64
Shot or Treated.
Contractor. Stickle Drlg.
Issued. 4-4-64

County Hodgeman
KANSAS



Elevation. 2045' KB (2405)

Production. DRY

CASING:

8" 282' cem w/ 225 sx

Figures Indicate Bottom of Formations.

post rock	60
shale & shells	1383
red beds	1593
anhydrite	1642
red bed & shells	1805
shale & lime	2790
broken lime	2925
shale & lime	3645
shale	3708
lime	3800
shale & lime	4059
lime	4160
cherty lime	4253
lime	4388
sand, chert & shale	4415
lime	4446
lime & chert	4491
lime	4585
Total Depth	

TOPS: SCOUT

Herrington	2383
Winfield	2432
Fort Riley	2558
Base Fort Riley	2628
Tarkio	3217
Topeak	3439
Council Grove	2723
Admire	3019
Wabaunsee	3108
Heebner	3720
Lansing	3765
Base Kansas City	4154
Marmaton	4184
Cherokee	4296
Conglomerate	4390
Mississippi	4438