

LARNED

Form 113 50M 4-49—47450-D

State Kansas County Pawnee

Sec. 28 Twp. 21 Rng. 16w Elev. 2025

Company Sunray

Well No. 1 Name Brown

Location NE NE SW

Feet from lines: N. S. E. W.

Spud 5-22-49 Completed 8-3-49

T. D. 3881½ Casing 8" 1010, 5" 2881½

Comp. Perf. 4' 3877½-78½

Pay 3877½-78½ Arbuckle

I. P. 80 BOPD

Choke T. P. C. P.

G. O. R. Grvty.

DATE	REMARKS
8-3-49	Ann 1007, Heeb 3412, BrL 3509 LKc 3520, BKe 3729, Cong 3835 SSh 3846, Arb 3851, 3872- 78½ rec 4' dolo, gassy, gd

686824

bug por at btm, DST 3873 $\frac{1}{2}$ -78 $\frac{1}{2}$ /30
 min 100' oil, 50' OCM, est 3,000,000
 cfg, DD 3881 $\frac{1}{2}$, fr por, lt stn, DST
 3876 $\frac{1}{2}$ -81 $\frac{1}{2}$ /30 min/ 120' oil & 120'
 muddy oil & 60' wtr. BHP 1750#
 est 2,000,000 CFG. Shhl. DST 3855-
 67/10 gas 1/2 M est 4 to 5 MCFG,
 Ø 3867-72 rec 3' fine crystalline
 por dol. SSO. DPTD, Gamma Ray 4 Ø
 3877 $\frac{1}{2}$ -78 $\frac{1}{2}$ flow 4 to 5 BOPH & 4 $\frac{1}{2}$
 MCFG. Ext flow 40 BOPD & 4 $\frac{1}{2}$
 MCFG. Flow 1/2" choke 72.8 BOPD &
 3 MCFG. 2 1/4" ck flow 80 BOPD &
 2 M 8 1/4 TCFG.
 P 80 BOPD (Gas contains no BTU)

COMPLETE.

REMARKS

DATE