

State Kansas County McPherson

Company Messman-Rinehart Oil Co. Well No. 1

Farm Martin Goering


Survey

Block No. 28 Sec. 21 Twp. S Range 2 W

Co-Ord. Elev. 1468' K/B

SE SE NE

M-R Rig



50% - A. A. Seeligson, Jr.
25% - Chicago Group
25% - Messman-Rinehart Oil

F0 - W.L. Hartman
Geol. - B. Frensey
To be comm. 60 days from
3/6/63

3600' Sp. test

NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line

Ft. from S. Line

Ft. from W. Line

Ft. from E. Line

Date

Depth

4/26/63		M.I.R.T. - Spud - 8-5/8" @ 250' w/180 sx. cem., 4 gel &
		4 c.c., P.D. @ 1:00 a.m. 4/27
4/29	925	Drlg.
4/30	1690	Drlg.
5/1	2170	Drlg. (#3 @ 1957)
5/2	2525	Drlg.
5/3	2711	Drlg.
	1935	Topeka (-467)

Date	Depth	10669 (-10) 694363
	2082	Heebner (-614)
	2105	Douglas (-637)
	2344	Lansing (-876)
DST #1	- 2649-2711	- Op 1 hr., good blow TO
		Rec. 1440' SW, BHP (30'') 1128-1122,
		FP 184-695#
5/4	2855	Drlg. (#5 @ 2711)
	3022	Miss. (-1554)
DST #2	- 3024-351	- Op 1 hr., strong blow TO
		Rec. 10' mud, BHP (30'') 839-533#,
		FP 16-16#, Temp. 110°
DST #3	- 3035-501	- Op 1 hr., GTS in 1 hr.,
		Rec. 30' gas-cut mud, BHP (30'')
		954-809#, (bldg.), FP 28-40#, Temp 107°
5/6	D.S.T. #4	- 3053-701 - Op 1 hr., fair blow TO
		GTS in 85" (25" min. after tool SI)
		Rec. 45' sli GCM, BHP (30'') 960-948#
		FP 22-28#, Temp. 107°
		3090 Drlg.
DST #5	- 3070-3100	- Op 1 hr., fair blow,
		Rec. 120' very sli OC mdy SW, 60' SW
		BHP (30'') 972-881#, FP 52-100#, Temp 113°
5/7	3190	Drlg.
5/8	3289	Drlg.
	3333	Drlg. 4:00 p.m. lost circ.

State Kansas County McPherson

Company Messman-Rinehart Oil Co. Well No. 1


Farm Martin Goering

Survey _____

Block No. _____ Sec. 28 Twp. 21 S Range 2 W

Co-Ord. _____ Elev. 1468' K/B

SE SE NE



page 2

NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line		Ft. from S. Line
Ft. from W. Line		Ft. from E. Line
Date	Depth	
	3472	Drlg.
5/9/63	3394	Meisner (-1926)
	3396	Huntton (-1928)
	3415	Maquoketa (-1947)
	3505	Viola (-2037) no sho
	3520	Drlg.
5/10	3342	Kinderhook (-1874)
	3538	Simpson (-2070)
DST #6 - 3535-3552' - Op 1 hr., wk. bl. for 4		

Date

Depth

694363

14' broken Rec. 15' sour mud, BHP (30") 821-677#,
 sd & dol FP 28-34#, Temp. 116°

3556 Drlg.

3611 Arbuckle (-2143)

3628 R.T.D. (Ran log to 3627')

Dry and Abandoned

5/11/63