

A-5-136
MAP NO. 2-52

2913KB

ELEV. 2909DF, 2905GL

STATE Kansas COUNTY Finney SEC. 29 Twp 21S Rge 32W

OPERATOR Fortune Oil & Gas, Inc. - Wichita, Ks. LOC. C SW/4

WELL NO. 1 FARM NAME Greathouse FT. FROM _____ LINE _____

COL Hugoton, E. (PD 2750) FT. FROM _____ LINE _____

FR. 3-17-61 SPUD 4-4-61 COMP. 5-4-61

CONT./GEOL. S&S Tools Bob Jones-Geol.

NAME PRODUCING INTERVAL		COMPLETION RECORD	PERF. W/HOLES	TREATMENT RECORD
FROM	TO			
<u>Krider</u>	<u>2678-2702</u>		<u>72</u>	<u>F/6x4</u>

a I. P. OIL/DIST. WTR 72/20 Ga GAS 1704 M.C.F.P.D. _____ CHK. _____ HRS. _____

b " " " " " " " " " "

c " " " " " " " " " "

d _____

D & A ()

SIP# 395 FI TP # _____ FI CP# _____ SIBHP _____

GOR. _____ GR. _____ PBDT _____ TD 2755

SIZE	DEPTH	CASING - CEMENT RECORD	SIZE	DEPTH	W/SAX.
		W/SAX.			
<u>8 5/8"</u>	<u>295</u>	<u>300</u>			
<u>4 1/2"</u>	<u>2754</u>	<u>150</u>			

OPERATOR Fortune Oil & Gas WELL NO. #1 Greathouse ELEV. 2909 DF

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
Herrington	2644	+269			
Krider	2675	+238			
Winfield	2723	+180			

Spud 4-4-61, 8 5/8" @ 295 w/300 sx.

RTD 2750, logs to 2755. 4 1/2" @ 2754 w/150 sx. MICT. CO.

P/32/2678-86, 40/2692-2702, Frac 6000 Ac X 4000 sd, Flow 1d.

IP 72/20 Ga 1704 MCF, SIP 395, from Krider (2678-2702).

COMPLETE 5-4-61.