

Location. NWc SW

DEEPENING RECORD & CORRECTED LOG

Sec. 3 T. 21 R. 3W. Plotted Texas CO.

County. McPherson.

Casing Record.

10" Farm. J.P.Krehbiel
8 1/2" 3409 Company Gypsy Oil Co.
5 1/2" 65/8" Contr.
3 1/2" 198 53/16" Comm. 4- 5-30

No. 4

Comp. 5-26-30

Total Depth. 3504 Shot Quarts Between.

Correspondence Regarding This Well Should Be Referred To.

Elevation.

Figures Indicate Bottom of Formations.


Date Issued. 2-11-33

Initial Production.

Swabbed 844 B. and pumped

666 B. in 19 hrs. T.D. 3449 1/2

New Prod. Dry T.D. 3504.



B 11 1933

plotted

Formation	Depth.
clay and shale	198
clay and shale	206
shale and sand shells	430
lime and shale and shells	1050
shale and sand	1220
lime and shale	1445
broken lime	1500
shale and shells	1625
broken lime and shale	1770
lime	1915
shale	1967
lime	2045
shale and sand	2073
lime hard	2110
shale	2170
sand	2193
shale and sand	2250
lime	2273
shale and sand	2330
lime	2466
sand	2500
lime	2675
lime and shale	2880

SAMPLE LOG.

SHALE grey	2940
V.C.shale	2980
shals red	3030
chert	3130
lime	3160
shale	3405

Corrected measurement following depths all corrected.

lime white crystalline	3429
shale green and sand and dolomite	3438
sand T.D.	3449 1/2
Standardized at 3416 equals 3411' SLM.	

DEEPENING RECORD.

Old T.D.	3449 1/2
Comm. 12-10-32 Comp. 1-16-33.	
Prod.-Dry. and Abd.	
3449 equals 3447 S.L.M	
sand 3447-	3455
sdyl shale green	3495
dolomite	3504
TD.	

SWABBING AND PRODUCTION RECORD.

5-1-30 Swab 280 B. oil in 8H. 3449 1/2 ft.
5-2-30 Swab 844 B. oil in 24 hrs. 3449 1/2 ft
5-3-30 Swab 651 B. Oil in 15 hrs 3449 1/2
5-4-30 Swab 741 B. Oil in 23 hrs. 3449 1/2 ft
5-5-30 Swab 671 B. Oil in 18 hrs. 3449 1/2 ft
5-6-30 Swab 329 B. Oil in 12 Hrs. 3449 1/2 Ft.
5-7-30 Swab 657 B. Oil in 24 Hrs. 3449 1/2 Ft.
5-15-30 Swab 505 B. Oil in 21 hrs. 3449 1/2 ft.
5-20-30 Swab 100 B. oil in 5 Hrs. 3449 1/2 ft
5-24-30 Pump 410 B. oil 21 hrs. 3449 1/2 ft
5-26-30 Pump 666 B. Oil in 19 hrs. 3449 1/2 ft

12-19-32 Very small show of oil at 3498 ft.
Water level rose from 250 to 400 ft off bottom 3498-3499

Water level rose from 400 to 600 ft off bottom 3499-3502 1/2

Water level rose from 600 to 1000 ft off bottom 3502 1/2 to 3504.

12-28-32 Plugged back to 3464 feet.

12-29-32 shot with 40 qts from 3440 to 3453 feet, no oil showing.

1-6-33 Hole filled 500 ft with water in 3 hours no oil

1-16-33 Plugged and abd.

3504
3160
344