

4-21-30
 Plotted Texas Co.

WELL LOG BUREAU- KANSAS GEOLOGICAL SOCIETY

SEP 1 1930


UNION NATIONAL BANK BLDG, WICHITA, KANSAS

Location NW SW SE Rotary to 3382 Cable to 3421 Sec. 4 T. 21 R. 3W.
 330' East 990' N of S $\frac{1}{2}$ cor.

Casing Record Farm- August Krehbiel No. 6 County- McPherson.

20" 10"
 15 $\frac{1}{2}$ " 8 $\frac{1}{4}$ "
 15 $\frac{1}{2}$ " 163' 35/8" 3382
 12 $\frac{1}{2}$ " 53/16"
 Total Depth 3421 Shot Quarts Between
 Correspondence Regarding This Well Should Be Referred to

Company- Barnsdall Oil Co.
 Contr.- Mead Bros.
 Comm.- 6-26-30 Comp.- 7-27-30



Figures Indicate Bottom of Formations.
 Date Issued: 8-30-30

Elevation
 Initial Production 620 bbls.
 swab 22 hrs.

Formation	Depth.	Sand Record.	Elevation
soil and shale	176		
shale lime	469	Chat	3050-94
sand	490	Viola lime	3379-3393
shale and lime shells	780	Wilcox sand	3405-3421
lime	902		
shale shells	950	Core Record	
broken lime	975	3351-3366	Recovery all shale.
shale shells	1400	3366-3382	shale 3366-3379
broken lime	1455	lime 3379--3382.	
shale shells	1539		
broken lime	1568		
shale lime	1627		
lime	2065		
shale lime	2109		
lime	2198		
broken lime	2309		
lime shale	2390		
lime	2466		
shale	2510		
broken lime	2553		
lime	2591		
sd lime	2724		
sand	2736		
lime shale	2780		
broken lime	2942		
broken lime and shale	3006		
shale	3010		
sand	3020		
shale shells	3045		
shale gyp	3050		
chat	3094		
lime	3098		
shale lime	3197		
shale	3220		
broken lime	3252		
shale	3379		
lime (Viola)	3393		
shale Green	3405		
sand (oil)	3421		

Total Depth.