

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

*Plotted
Albert H. ...*

SINCLAIR PRAIRIE OIL CO.
J.A. Krehbiel No. 3


SEC. 4 T. 21 R. 3W.
NE 8E
225' fr Nth 225' fr E. 8 1/2
SE 1/4

DEEPENING RECORD.

Plotted Texas CO.
County, McPherson.

Total Depth. 3493 P.B. 3486 1/2
Comm. 4-8-30 Comp. 6-4-30
Shot or Treated.
Contractor.
Issued. 8-14-37

AUG 14 1937



CASING.

15 1/2" 179'
8 1/4" 3012'
65/8" 3370'
53/16" liner 182' set at 3480

Elevation.

Production. 350 B.

Figures Indicate Bottom of Formations.

surface 30
sand 90
shale 100
sand shale 150
shale 179
sand & limo shells 340
shale 400
limo shells 430
shale and shells 790
shale limo shells 1040
shale and shells 1490
shale 1545
lime shells 1620
shale 1725
shale sdy lime 1815
broken lime 1945
shale 1975
lime 2015
shale 2110
lime 2125
shale and shells 2220
broken lime 2265
sand 2300
broken lime 2350
lime 2480
broken lime 2525
broken lime 2630
lime 2790
broken lime 2990
shale 3012
cement 2998-3008
chat 3105
lime white 3150
shale blue 3180
shale 3185
shale blue 3200
shale blue 3355
sdv shale 3385

Viola lime 3418
shale green 3422
Wilcox sand 3445
sdv shale 3456
Total Depth.

DEEPENING RECORD.

Comm. 11-3-36
Comp. 12-2-36
Prod. Pot. 60 bbls oil 125 bbls wtr.
average on two day test.

sdv shale 3460
Wilcox sand 3463
shale dark 3465
Wilcox sand 3469
Bluish green shale 3477
Wilcox sand 3478
shale dark green 3480
Wilcox 3493
Total Depth. P.B. 3486 1/2