

Company- SINCLAIR OIL & GAS & GULF OIL CORP., et al SEC. 4
Farm- A. E. Morehouse No. 12

T. 21 R. 3W
C 3/2 N/2 NE
990' SNL 1320' EWL

4-21-3W

Total Depth. 4450'

Comm. 12-8-56

Comp. 1-14-57

Shot or Treated.


Contractor. Sinclair Oil & Gas & GULF OIL CORP., et al

Issued. 2-8-58

County

McPherson

KANSAS



CASING:

9 5/8" 791' cem w/400 sx

7 " 3491' cem w/650 sx

Elevation. 1454 D.F.

Production. SWDW

Figures Indicate Bottom of Formations.

shale	60
sand & shale	385
Anhydrite & shale	525
shale & shells	670
shale & lime	780
Anhydrite	840
lime	940
shale & lime	1910
lime	2125
shale & lime	2380
lime	2962
Mississippi chert	2992
Mississippi lime	2997
lime & shale	3030
shale	3285
lime & shale	3300
lime	3336
sand - hard	3351
sand	3421
lime	3695
Cherty lime	3745
lime	3970
lime & sand	3995
sand	4011
sand & lime	4045
sand	4056
sand & lime	4139
sand	4165
sand & lime	4172
sand	4185
sand - hard	4200
sand & granite	4305
sand	4319
Granite & sand	4353
sand	4375
Granite & sand	4412
sand	4431
Granite & sand	4450
Total Depth	

TOPS: SCOUT

Mississippi	2962
Viola	3287
Simpson	3318
Arbuckle	3392
Reagan	3920
Pre Cambrian	3996

Open hole completion from 3491-4450'.
Acidized w/5000 gallons acid