

24165

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY

UNION NATIONAL BANK BLDG, WICHITA, KANSAS


Location NEc NW SE

Sec. 9 T. 21 R. 3W

Casing Record

County- McPherson

20" 10" Farm- Stucky No. 3
15 1/2" 168 8 1/4" 2968 Company- Derby Oil Co.
12 1/2" 53/16" 65/8" 368 Contr.- L.W. Prunty.
Total Depth 3389 Comm.- 1-25-30 Comp.- 4-18-30
Correspondence Regarding This Well Should Be Referred to Shot Quarts Between



Elevation

Figures Indicate Bottom of Formations.
Date Issued. 7-5-30

Initial Production
Swab 100 Bbls.

Formation	Depth	Formation	Depth	Formation	Depth.
surface clay	25	broken lime	1412	shale	2522
sand wtr	49	sdv lime	1422	lime	2532
sand and gravel	127	lime	1487	sdv lime	2557
shale	369	sticky shale	1494	sand	2573
broken lime	391	lime	1518	lime hard	2694
lime	410	sticky shale	1523	shale	2704
shale	456	lime	1528	lime	2714
broken lime	486	broken lime	1563	sticky shale	2724
lime brown	506	lime	1571	lime	2729
shale	526	sticky shale	1597	sdv lime	2743
broken lime	566	lime	1607	lime	2762
shale	576	sticky shale	1655	shale&lime	2802
broken lime	592	shale & shells	1665	2802=2826 SLM	
shale	607	lime	1718	lime 2826--2831	
lime	617	sticky shale	1728	lime and shale	2845
shale	667	lime	1783	lime	2860
sand	682	Gypsum	1788	sticky shale	2870
sdv lime	707	lime	1866	lime	2878
shale	777	shale	1876	sticky shale	2893
lime	792	lime	1904	shale&lime	2911
broken lime	815	sdv shale	1926	lime	2921
shale and shells	836	lime	1984	shale	2944
lime	846	shale brown	1991	lime	2961
broken lime	925	lime	2052	red bed	2967
lime	945	broken lime	2102	chat	3020
sand and lime	965	sdv lime	2118	shale	3267
broken lime	995	lime	2125	lime	3292
sand	1001	shale	2153	Show oil cored	3292-
broken lime	1044	sdv lime	2186		99
sticky shale	1054	shale & shells	2256	lime	3299
shale and shells	1084	sand	2263	shale	3305
broken lime	1120	shale & shells	2278	sand	3307
sand	1135	broken lime	2314	shale blue	3326
sticky shale	1145	sdv lime	2323	sand WILCOX	3343
lime	1170	lime	2341	sand&shale	3375
broken lime	1200	sticky shale	2359	shale green	3382
shale and shells	1260	sdv lime	2394	3200' oil in hole	
sticky shale	1311	lime	2429	lime	3389
sdv lime	1326	sdv lime	2454	oil filled to top.	
sticky shale	1364	lime	2472	swabbed 100 bbls.	
shale and shells	1377	sdv lime	2502	Total Depth	3389

PRODUCTIONS.

1504 bbls. 4-16-30
2656 Bbls. 4-17-30 24 hrs.
1992 bbls. 4-19-30 #3 @ #6