


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY

UNION NATIONAL BANK BLDG., WICHITA, KANSAS.

Location NE c SE/4 (DEEPENING RECORD) Sec. 9 T. 21 R. 37.
330' fr NL 345' fr EL SE/4

Casing Record County- McPherson.

20" 10" 175 Farm- Stuckey No. 1
15 1/2" 8 1/4" 2981 Company- Derby Oil Co.
12 3/4" 65/8" 3277 Contr.- L. W. Prunty Drlg. Co.
12 3/4" 53/16" Comm.- 8/4/1929. Comp.- 10/3/1929.
Total Depth 3395' Shot Quarts Between
Correspondence Regarding This Well Should Be Referred to



Figures Indicate Bottom of Formations.

Date Issued.

Elevation
Initial Production 1400 bbls.

4/19/30

CORRECTED LOG

Formation	Depth	Formation	Depth
sand	90	lime	2540
shale	100	shale	2545
sand	120	lime	2573
shale	390	sand	2580
lime	400	lime	2603
shale	440	shale	2611
lime	455	lime	2680
shale & shells brkn	575	lime brkn	2713
lime brkn	655	shale	2740
shale	717	lime	2765
lime	857	shale (Trace of red chat rock 3004')	2976
shale & shells	1340	1 3/4 M. ft Gas.	3003
slate	1440		
lime hrd	1460	lime	3012
shale & shells	1520	lime white	3025
slate	1570	shale	3096
shale sticky	1610	lime	3100
lime brkn	1655	shale	3282
lime	1720	sdv lime	3286
shale sticky	1730	sand	3290
sand	1740	sdv lime	3292
lime	1757	sdv lime hrd	3295
shale sticky	1783	sdv lime	3300
lime	1840	lime hrd sandy	3307
shale sticky	1860	lime brown	3310
lime	1865	slate & sdv lime	3315
shale	1881	sandy grey lime	3318
lime	1982	sdv lime	3322
lime brkn	1992	sand grey	3325
shale	2055	Hole filled up with oil	
lime	2095	1500' in 1 hr.	
sand	2245	sand	3335
shale	2260	sand	3341
sandy shale	2310	brkn sand & lime	3357
shale	2365	lime	3361
lime	2380	sand & shale	3375
lime sdv hrd	2400	sdv lime	3382
shale	2410	oil sand	3394
lime	2417	oil sand	3395
lime sdv	2466	Total Depth	3395
lime	2480		
sand	2490		

Increase of Oil 1400 bbls.

Top of Chat 2976
Top of Viola 3266
Top of Wilcox 3322
Top of Siliceous
lime 3375?