


IND



DRILL STEM TEST REPORT

Prepared For: **Raydon Exploration, Inc.**

1601 NW Expwy, STE 1300 Oklahoma City,

OK 73118

CONFIDENTIAL

APR 09 2009

ATTN: Ed Grieves

KCC

21 21 31 Finney KS

Uhland 1-21

Start Date: 2009.03.01 @ 08:12:21

End Date: 2009.03.01 @ 19:37:50

Job Ticket #: 30853

DST #: 1

Trilobite Testing, Inc

PO Box 1733 Hays, KS 67601

ph: 785-625-4778 fax: 785-625-5620



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

Raydon Exploration, Inc.

1601 NW Expwy., STE 1300 Oklahoma City, OK
73118

ATTN: Ed Grieves

Uhland 1-21

21 21 31 Finney KS

Job Ticket: 30853

DST#: 1

Test Start: 2009.03.01 @ 08:12:21

GENERAL INFORMATION:

Formation: **Atoka**

Deviated: **No** Whipstock: **ft (KB)**

Time Tool Opened: 11:41:50

Time Test Ended: 19:37:50

Test Type: **Conventional Bottom Hole**

Tester: **Chris Hagman**

Unit No: **34**

Interval: **4680.00 ft (KB) To 4720.00 ft (KB) (TVD)**

Total Depth: **4720.00 ft (KB) (TVD)**

Hole Diameter: **7.78 inches** Hole Condition: **Good**

Reference Elevations: **2912.00 ft (KB)**

2901.00 ft (CF)

KB to GR/CF: **11.00 ft**

Serial #: 6753 **Inside**

Press@RunDepth: **32.29 psig @ 4682.00 ft (KB)**

Start Date: **2009.03.01**

End Date:

2009.03.01

Start Time: **08:12:21**

End Time:

19:37:50

Capacity: **7000.00 psig**


Last Calib.: **2009.03.01**

Time On Btm: **2009.03.01 @ 11:41:30**

Time Off Btm: **2009.03.01 @ 16:14:40**

TEST COMMENT: IF: Weak surface blow, died 15 min.
IS: No blow back
FF: Weak surface blow, died 5 min.
FS: No blow back

Pressure vs. Time



PRESSURE SUMMARY

Time (Min.)	Pressure (psig)	Temp (deg F)	Annotation
0	2383.59	113.29	Initial Hydro-static
1	24.30	112.78	Open To Flow (1)
32	24.80	113.61	Shut-In (1)
93	919.89	115.18	End Shut-In (1)
93	29.16	114.91	Open To Flow (2)
155	32.29	115.86	Shut-In (2)
273	908.23	117.59	End Shut-In (2)
274	2283.02	117.25	Final Hydro-static

Recovery

Length (ft)	Description	Volume (bbl)
20.00	oil spotted mud 100%M	0.10

Gas Rates

	Choke (inches)	Pressure (psig)	Gas Rate (Mcf/d)
--	----------------	-----------------	------------------



**TRILOBITE
TESTING, INC**

DRILL STEM TEST REPORT

TOOL DIAGRAM

Raydon Exploration, Inc.

Uhland 1-21

1601 NW Expwy, STE 1300 Oklahoma City, OK
73118

21 21 31 Finney KS

Job Ticket: 30853

DST#: 1

ATTN: Ed Grieves

Test Start: 2009.03.01 @ 08:12:21

Tool Information

Drill Pipe:	Length: 4370.00 ft	Diameter: 3.80 inches	Volume: 61.30 bbl	Tool Weight:	2000.00 lb
Heavy Wt. Pipe:	Length: 0.00 ft	Diameter: 0.00 inches	Volume: 0.00 bbl	Weight set on Packer:	20000.00 lb
Drill Collar:	Length: 292.00 ft	Diameter: 2.25 inches	Volume: 1.44 bbl	Weight to Pull Loose:	70000.00 lb
		Total Volume:	62.74 bbl	Tool Chased	0.00 ft
Drill Pipe Above KB:	10.00 ft			String Weight: Initial	52000.00 lb
Depth to Top Packer:	4680.00 ft			Final	52000.00 lb
Depth to Bottom Packer:	ft				
Interval between Packers:	40.00 ft				
Tool Length:	68.00 ft				
Number of Packers:	2	Diameter:	6.75 inches		

Tool Comments:

Tool Description

Tool Description	Length (ft)	Serial No.	Position	Depth (ft)	Accum. Lengths
Change Over Sub	1.00			4653.00	
Shut In Tool	5.00			4658.00	
Hydraulic tool	5.00			4663.00	
Jars	5.00			4668.00	
Safety Joint	3.00			4671.00	
Packer	5.00			4676.00	28.00 Bottom Of Top Packer
Packer	4.00			4680.00	
Stubb	1.00			4681.00	
Perforations	1.00			4682.00	
Recorder	0.00	8374	Inside	4682.00	
Recorder	0.00	6753	Inside	4682.00	
Perforations	2.00			4684.00	
Change Over Sub	1.00			4685.00	
Drill Pipe	31.00			4716.00	
Change Over Sub	1.00			4717.00	
Bullnose	3.00			4720.00	40.00 Bottom Packers & Anchor
Total Tool Length:	68.00				



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

FLUID SUMMARY

Raydon Exploration, Inc.

Uhland 1-21

1601 NW Expwy, STE 1300 Oklahoma City, OK
73118

21 21 31 Finney KS

ATTN: Ed Grieves

Job Ticket: 30853

DST#: 1

Test Start: 2009.03.01 @ 08:12:21

Mud and Cushion Information

Mud Type: Gel Chem

Cushion Type:

Oil API:

deg API

Mud Weight: 9.00 lb/gal

Cushion Length:

ft

Water Salinity:

2700 ppm

Viscosity: 51.00 sec/qt

Cushion Volume:

bbl

Water Loss: 7.59 in³

Gas Cushion Type:

Resistivity: ohm.m

Gas Cushion Pressure:

psig

Salinity: 3000.00 ppm

Filter Cake: inches

Recovery Information

Recovery Table

Length ft	Description	Volume bbl
20.00	oil spotted mud 100%M	0.098

Total Length: 20.00 ft Total Volume: 0.098 bbl

Num Fluid Samples: 0

Num Gas Bombs: 0

Serial #:

Laboratory Name:

Laboratory Location:

Recovery Comments: RW=3.057@50F=2700ppm

Serial #: 6753

Inside

Raydon Exploration, Inc.

21 21 31 Finney KS

DST Test Number: 1

