


**

State KS Field W.C.
 Company C.O.G. County FINNEY
 Farm CRIST No. 1
 Sec. 31 Twp. 21 Range 33

Spot NW SW

Contractor GARVEY

Remarks 4800'



Comm. 8-16-57 Comp. 11-20-57

Elev. DF 2908. GL 2903 KB TD 4950 PB 2620

Pay HER 2500-06 KRI 2531-55

WIN 2579-95

I.P. ^{3PT BPT} 5,580 MCF Press. SIP 4429

Casing Record: 13 3/8 7" 2830/100

20" 10 3/4 5 1/2"

16" 8 5/8 275/300 4 1/2 4896/120

LOC.	Sample	Log
<u>AUG 21</u> <u>φ 2550</u>	<u>HER 2498</u>	<u>HER 2502</u>
<u>AUG 28</u> <u>DST 2640-65</u>	<u>KRI 2538</u>	<u>KRI 2532</u>
<u>op 2 hr. GTS 25"</u>	<u>Heeb 3782</u>	<u>WIN 2580</u>
<u>g 36 MCF/30" g 93 MCF/2 hr</u>	<u>LANE 3817</u>	<u>U/PIR 2639</u>
<u>rec 155' GCM</u>	<u>BKS 4287</u>	<u>L/ " 2703</u>
<u>FPGO-80 BHP 455/30</u>	<u>CHER 4412</u>	<u>Heeb 3785</u>
<u>ITD 2840 rem log</u>	<u>MOR 4618</u>	<u>LANE 3833</u>
<u>7" φ 3470</u>	<u>MISS 4646</u>	<u>MOR 4616</u>
<u>SEP 4</u> <u>DST 4158-66</u>		<u>MISS 4626</u>
<u>op 2 1/2" rec 935' G</u>		<u>St. GEN 4639</u>
<u>Sulphur Wra. FP 110-625</u>		<u>St. LO 4669</u>
<u>BHP ?</u>		<u>SPURG. 4927</u>
<u>DST 4383-4400 op 1 3/4</u>		
<u>rec 130' SWCM FP 25-78</u>		
<u>BHP 1212/45" φ</u>		
<u>SEP 11</u> <u>DST 4427-38</u>		
<u>op 1 hr. rec 3' M FP 0 BHP 269/30</u>		
<u>DST 4459-70 op 1 hr. rec 4' SOCM</u>		
<u>all press 0 SF 30"</u>		
<u>DST 4522-34 op 2 hr. rec 210' G</u>		
<u>+ 90' oil (GRAV. 31°) 35' HO CM</u>		
<u>FP 100 BHP 1025/30</u>		
<u>DST 4542-62 op 2 hr. rec 5' SOCM</u>		
<u>FP 10-20 BHP 20/30</u>		
<u>to DST 4648-4748</u>		<u>ITD 4748 prep</u>

613345

SEP 18 DST 4648-4748 (57 20)
 op 2 hr see 135' G in DP 105' oil CM
 60' MGCO GRAV 290 FP 20-100
 BHP 985

30 DST 4749-87 op 1 hr. see
 10' M all press 0
 DST 4790-4816 op 45" see 3' M
 FP 10 BHP 55/30 RTD 4951
 near log ~~running~~ 4 1/2

SEP 23 4 1/2 RUCT CO G/R
 Pf 36/4742-51 MA/500 N.S. prep.
 to Aridge

OCT 2 A/4000 swab 9B sulphur wt.
 + sli sho 0.8G. PK @ 4694 19/250
 CO 4714 Pf 16/4682-86 20/4687-94
 32/4703-11 T & PK to 4650 MA/500
 A/2000 (didn't take) pulled T & PK
 CO, see Pf. 16/4682-86 20/4689-94
 32/4703-11 ~~running~~ T

OCT 9 MA/500 swab N.S. pulled T & pk
 set @ 4677 19/170 Pf 12/4672-75
 12/4665-68 ran T 4674 PK 4641
 MA/300 + A/3000 swab 35 gal fluid / PH
 (slip. oil) swab 4 gal fluid PH (50%
 oil) 7 1/2/6000 sd/1500 swab 15 to 20
 gal oil PH + ~~75~~ Acid wt. swab 15 gal
 oil + 30 gal acid wt. PH, pulled T
 dumped 2 sacs cement on Pf 4665-75
 prep to Pf. Cherokee

OCT 16 pl @ 4575 Pf 44/4528-39 16/4546-50
 ran T & PK @ ? MA/500 swab
 10-12 gal O + 65-70 gal wtr PH
 24 hr. swab 12 gal O + 70 gal wtr / PH
 A/3000 swab load + 80 gal O + 30 gal wtr
 + sli sho gas late swab 40 + 70
 A/7500 swab 20 BO + 40 B wtr in 16 hr.
 " 17 " + 24 " in 18 hr.
 swab 2 B fluid PH 50% oil

OCT 8 S swab 17.5 B wtr + 20 BO in 24 hr.
 GRAV 31° pulled T set pl @ 2800
 Pf 32/2638-46 MA/500 swab g TSTM A/4000
 g 27MCF + 35 gal wtr. PH 19/230 pl 2620
 Pf 40/2585-95 12/2579-82 A/6000 swab g 27MCF
 + 20 gal WPH g 36MCF + 4 gal WPH TST.

OCT 30

PL @ 2566 96/2531-55 g 520 MCF dry
A/1000 FR/25,000 SA/10,000 swab
g 5,000 MCF + wti. spray φ pl C02620
PL @ 2518 pt 24/2500-06 A/3000
g 3,500 MCF + 35 gal wti PH pow. comm.
φ pl C02620 g 3,600 MCF + mist

NOV 6

20" g 10,800 MCF dry (PEDO-TUBE GAGE)

NOV 13


NOV 20

3 PT

BPT

C0F 5,500 MCF

SIP 442.9



AMARILLO TOPS

2911 KB

Winfield 2580 (-331)

Heebner 3788 (-877)

Lansing 3833 (-922)

Morrow 4615 (-1704)

Chester 4626 (-1715)

St. Gen 4639 (-1728)

St. Louis 4666 (-1755) tst'd 15 GO / 30 GWPH

Spergen 4928 (-2017)

TD 4953 (-2042)