

MAP NO. _____ 2-23-61 ELEV. 2916KB 2913DF
 STATE Kansas COUNTY Finney SEC. 31 Twp 21 S Rge 33 W
 OPERATOR Nate Appleman Co., New York LOC. C NW NW
 WELL NO. 2 FARM NAME Maune FT. FROM _____ LINE _____
 OL WILDCAT (PD 4600) FT. FROM _____ LINE _____
 FR. 11-30-60 SPUD 12-8-60 COMP. 2-15-61

CONT./GEO. E. F. Wakefield Drilling tools.

COMPLETION RECORD			
NAME PRODUCING INTERVAL	FROM - TO	PERF. W/HOLES	TREATMENT RECORD
a <u>Ste Genevieve</u>	<u>4654-73</u>	<u>76</u>	<u>6500 Ac-F/20X10</u>
b _____	_____	_____	_____
c _____	_____	_____	_____
d _____	_____	_____	_____

a I. P. OIL/DIST. P/28 BOPD WTR. 30% GAS _____ M.C.F.P.D. _____ CHK. P HRS. 24
 b " " " " " " " "
 c " " " " " " " "
 d _____

D & A ()

SIP#	FI TP #	FI CP#	SIBHP
GOR. _____	GR. <u>26.6°</u>	PBTD <u>4700</u>	TD <u>4731</u>

CASING - CEMENT RECORD	
SIZE	DEPTH
<u>8-5/8"</u>	<u>343</u>
<u>5 1/2"</u>	<u>4731</u>

OPERATOR Nate Appleman Co. WELL NO. 2 Maune ELEV. 2916 KB

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
Blaine	1340		Blaine	1347	
Cimarron-			Wellington	2343	
Anhydrite	1905		Hollenburg	2522	
Stone Corral	2050		Winfield	2583	+333
Weelington	2355		Upper Ft. Riley	2647	
Hollenburg	2495		Neva	3004	
Herrington	2525		Topeka	3498	-582
Winfield	2575		Heebner	3782	
Upper Ft. Riley	2645		Lansing	3805	-889
Topeka	3504		Marmaton	4247	
Lansing	3801		Cherokee	4455	
Marmaton	4268		Atoka	4594	
			Morrow	4622	-1706
			Ste. Genevieve	4651	-1735
			St. Louis	4681	-1765

Spud 12-8-60. 8-5/8" @ 343 w/250 sx.
 DST # 1 (Chero) 4525-70, op 1 hr, wk blo/died 21 mins, rec 4' M, ISIP 60/30 mins, FP 20-20, FSIP 40/30 mins.
 CORE # 1 4659-80, rec 21' - 1' lm, slt stn, 1' sdy sh/stn, 2' sd gd stn, 2' lm, vert frac, bldg oil, 6' lm/NS, 6' sh,