

KANSAS DRILLERS LOG

State Geological Survey
WICHITA, BRANCHAPI No. 15 — 055 — 20,139
County Number

Operator

Marjice L. Brown Trust & I. W. Woolsey

Address 1500 Vickers KSB&T Bldg., Wichita, Kansas 67202

Well No.

#3

Lease Name

R. Crist

Footage Location

1980 feet from (N) (S) line 660 feet from (E) (W) line

Principal Contractor

SAGE DRIG.

Geologist

CLARK ROACH

Spud Date

6-19-74

Total Depth

4730

P.B.T.D.

Date Completed

7-9-74


Oil Purchaser

NCRA

S. 31 T. 21 R. 33 W

Loc. C NE SE

County Finney

640 Acres
N

Locate well correctly

Elev.: Gr. 2815

DF KB 2900

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
surf.	12 1/4	8 5/8	28	366	HLC COMM	300	3% CC 1/4" floccle/sk
Production	7 7/8	5 1/2	14-17	4703	HLC COMM	250	2% CFR-2 1/2" S.T.F. 65% comm 35% BZ.

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
				OPEN-HOLE	4703-4730

TUBING RECORD

Size	Setting depth	Packer set at
2"	4724	—

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
500 GAL 15% MCA	4703-30

INITIAL PRODUCTION

Date of first production	7-27-74	Producing method (flowing, pumping, gas lift, etc.)	Pump
RATE OF PRODUCTION PER 24 HOURS	Oil 125 bbls.	Gas — MCF	Water 0 bbls.
Disposition of gas (vented, used on lease or sold)	—	Producing interval (s)	4703-30

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator <i>The M.B. Brown Co.</i>		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. <i>3</i>	Lease Name <i>R. CRIST</i>	<i>OIL</i>
S <i>31</i> T <i>21</i> R <i>33</i> E <i>(W)</i>		

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
<i>φ 1-2-3-4</i> <i>DST # 3</i> <i>45-45-60-90</i> <i>Rec: 1650' HOCM.</i> <i>FP- 373 - 759 *</i> <i>SIP- 834 - 834 *</i>	<i>4638</i> <i>4703</i>	<i>4730</i> <i>4730</i>	 <i>MISS.</i>	 <i>4610</i>

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received 	
	Signature <i>Chief Eng.</i>
	Title <i>1-21-75</i>
	Date