

3-357W

MAP NO.

52

SEC. 31-21S-33W

STATE Kans.

COUNTY

Finney

LOC C NE NW

OPER The Shallow Water Ref. Co., Wichita, Kansas

FT/FR LINE

WELL #4 FARM Maune

FT/FR LINE

COL Nunn East

ELEV. 2895 GR. 2898

DF 2901

KB

CONT. Leben Drlg. Tools

GEOLOGIST R. W. Lang

C. INT. 4850' Miss test


FR. 8/14/63 SPUD 8/15/63 COMP. 3/24/64

TD. 4780 FM St Lou PSTD 1900

COMP. RECORD 8-5/8" @ 376 w/425 sx.

5 1/2" @ 4735 w/100 sx.

SWDW in Glorietta



Data Inc.

KB Spl Tops:							
Grnhrn	370 +2531	B/SC	2045 + 856	Marm	4259 -1358		
Graner	470 +2431	Well	2330 + 571	Cher	4446 -1545		
Dak	545 +2356	Herr	2527 + 374	Atoka	4585 -1684		
Kiowa	785 +2116	Winf	2565 + 336	Morr	5615 -1714		
Cheyenne	890 +2011	UFR	2634 + 267	Miss	4657 -1756		
Perm	1035 +1866	Neva	2995 - 94	St L	4672 -1771		
Blaine	1355 +1546	Top	3475 - 574	RTD	4780 -1879		
B/"	1535 +1366	Hb	3760 - 859				
imm	1905 + 996	Lans	3781 - 880				

- ⊙ #1 (Morr) 4628-54, 3' sh w/oil stain, 8' black sdy sh, 6' sh green tite, 9' black sh glauc w/sh lam (Morr & Miss)
- ⊙ #2 (Morr) 4654-80, 3' black sh carb sdy, 3' sd br dense, 2' sd gray glauc, 3' Cg green waxy sh & lm, 2' lm stain, bleed oil, 4' lm, oil stain, bleed oil, 1' sh, 3' lm grey dns frac w/oil stn, 1' sd tan calc, 1' lm oil stain
- ⊙ #3 (Miss) 4730-4780, Rec 50' Lm scatted frac w/oil stain
- ⊙ #4 (St L) 4730-4780, 5' Lm light tan buff dns, 4' Lm br, 11' Lm oil stain to show free oil, 24' lm oil stain in part, 6' Lm tan dnse NS, RTD 4780, No log, 5 1/2" @ 4735 w/100 sx., Pipe collapsed, could not mill out, PSTD 1900', Ran GRN Log, Pf Glorietta 40/1565-75, no treatment, SWDW in Glorietta, 1565-75, COMPLETE (3/18/64)