


State Kansas Field Wampler
Company Imperial Oil of Kansas County Finney
Farm Hyer No. 3
Sec. 16 Twp. 21S Range 33W

Spot C SW SE
Contractor Co. Tools 5800'

Remarks _____



Comm. 4-7-60 Comp. _____
Elev. DF 2894 GL KB 2897 TD PB
Pay Krider 2553-76

I.P. _____ Press. _____
Casing Record: 13 3/8 7"
20" 10 3/4 4 1/2" 2673/75
16" 8 5/8 222/175

	Log	Datum
DST 2527-90, op 1 hr, GTS	Kri 2550	
7 min, g 600 MCF/20 min &	Win 2601	
stab, rec 190' GCM, FP 60-	CG 2827	
100, SIP 450-460/20; Ø3200'	Hb 3809	
APR 20 Hb 3809 Tor 3825	Tor 3825	
Lan 3850 B/KC 4314	Lan 3850	
Mrm 4336	B/KC 4314	
DST 4218-69 1hr.	Mrm 4336	
re 140' mdy wth	Chas 4482	
SI 1240-10 60 SI 20"	Mor 4622	
DST 4310-60 1hr.	ms	
re 15'm FSIP 250/20	St.G 4699?	
4465 (Mor 4622)		
APR 27 Chas 4482 Miss 4700		
DST 4615-75 Ø 30"		
re 20'm		
10IP 135/20"		
FSIP 50/20"		
RTD 4740 rmg log.		
MAY 4 WOCT		
MAY 11 log.	MAY 13 log MICT	
P92/2553-76		
A/5000 g 1,400 mcf		

613433

Ex 30 A X30 sd C'AD 8 74 x huc Tky
SI WOT

MAY 25

JUN 1

JUN 8

JUL 20

1

LIBERAL TOPS

2897 KB

Winfield 2601 (+296) (Kri perf g 8,000 MCF)

Heebner 3810 (-913)

Toronto 3822 (-925)

Lansing 3850 (-973) tst'd mdy wtr

Marmaton 4334 (-1437) tst'd Mud

Morrow 4614 (-1717) T 84', no sand, tst'd 20' Mud

No Sand

St. Gen 4698 (-1801)

RTD 4740