

A-8-7

MAP NO. K-52ELEV. E2898DF, 2896GLSTATE Kansas COUNTY Finney SEC. 15Twp 21S Rge 33WOPERATOR Musgrove Drilling CompanyLOC. C SE/4WELL NO. 1 FARM NAME Hobbs

FT. FROM _____ LINE _____

TOL Hugoton, Ext. (PD 2700)

FT. FROM _____ LINE _____

FR. 4-12-61 SPUD 4-10-61 COMP. 7-28-61CONT./GEOL. Chem-Tech Rig

NAME PRODUCING INTERVAL		COMPLETION RECORD		TREATMENT RECORD	
FROM - TO		PERF. W/HOLES			
<u>Herrington &</u>	<u>2591-2646</u>	<u>68</u>	<u>500Ac, F/25X25</u>		
<u>Krider</u>					

b Krider

c _____

d _____

a I. P. OIL/DIST. _____ WTR. _____ GAS 6528 M.C.F.P.D. _____ CHK. _____ HRS. 1

b " " " " " " " "

c " " " " " " " "

d _____

D & A ()

SIP# E 460 FI TP # _____ FI CP# _____ SIBHP _____GOR. _____ GR. _____ PBDT _____ TD 2657

SIZE	DEPTH	CASING - CEMENT RECORD	SIZE	DEPTH	W/SAX.
<u>7"</u>	<u>350</u>	<u>125</u>			
<u>4-1/2"</u>	<u>2657</u>	<u>75</u>			

OPERATOR Musgrove Drlg. Co. WELL NO. #1 Hobbs ELEV. E 2898 DF

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
Herrington	2589				
Krider	2618				
B/Krider	2652				

Spud 4-10-61. 7" @ 350 w/125 sx.

DST #1 (Kri) 2621-57, op 1 hr, GTS/4½ mins, Ga 139 MCF, Stab, Rc 80' GCM, ISIP 480/30 mins, FP 140-160, FSIP 460/30 mins.

RTD 2657, Welex logs to 2657. 4-1/2" @ 2657 w/75 sx. MICT. CO to 2657.

P/52/2620-46, 16/2591-95, Ga 250 MCF, Nat, 500 MA, Swb 1d, Ga 1,039 MCF, Frac 25,000 Ac X 25,000 sd, Ga 7,429 MCF.

P Ga 6, 328 MCF/1 hr, from Herrington & Krider (2591-2646), SIP E 460.

COMPLETE 7-28-61.

LIBERAL TOPS

613466

est. 2898 DF

Krider 2618 (+280) ϕ g 6,528 MCF

TD 2657