

12-254W 52 ✓ MAP NO. 2913 GR ELEV. 2915DE 2917KB
 STATE Kans COUNTY Finney SEC. 18 TWP. 21S RGE. 33W
 OPERATOR Texaco, Inc. LOC. C SW/4
 WELL NO. 1 FARM NAME J. U. Crist Unit FT. FROM _____ LINE _____
Hugoton FT. FROM _____ LINE _____
 FR. 11/10/61 SPUD 11/11/61 COMP. 12/27/61

CONT./GEOL. Sierra Pet. Co., Rig #4

COMPLETION RECORD

NAME PRODUCING INTERVAL FROM — TO PERF. W/HOLES TREATMENT RECORD

a Herr-Kri 2560-79 OH Frac

b _____

c _____

d _____

d I. P. OIL/DIST. _____ WTR. spray GAS 3791 M.C.F.P.D. _____ CHK. _____ HRS 24

b " " " " " "

c " " " " " "

d _____

D & A ()

SIP# _____ FI TP # _____ FI CP# _____ SIBHP _____

GOR. _____ GR. _____ PBDT 2579 TD 2600

CASING - CEMENT RECORD

SIZE DEPTH W/SAX. SIZE DEPTH W/SAX.

8 5/8" 217 150

4 1/2" 2560 450

OPERATOR Texaco, Inc. WELL NO. 1 J.U. Crist Unit ELEV. 2917 KB

SAMPLE TOPS DEPTH SUB SEA ELEC. TOPS DEPTH SUB SEA

KB Tops & Datums

Holl 2529 + 388

Herr 2546 + 371

RTD (Kri) 2600 + 317 Kri 2560 + 357

RTD 2600. Welex Log. 4½" @ 2560 w/450 sx. CO 2600 TD
 Ga 500 Mcfgpd/2 hrs, Tst dry, PB 2579. Sd Frac 20,000#
 sd x 2000 G Jell A, 5%, MP 1000#, Gas Ga 3188 Mcfgpd/19
 hrs + light spray AW, Ga 3100 Mcfgpd + 3½ BAWPH Ga 2232
 Mcfgpd + 11 BSWPH/24 hrs, SI/9 hrs, Op 20", Ga 3972 Mcfg
 pd, Ga 3040 M cfigpd (dry) 30", Ga 2481 Mcfgpd + 9 BWPB
 2½ hrs. Flow (OH 2560-79) Ga 1980 Mcfgpd + 6 BSWPH/24
 hrs, SI/72 hrs, SIP 410#. 72-20" Ga 3791 Mcfgpd w/spray
 SW, Herr Kri OH 2560-79, Est Allowable 948 Mcfgpd.

COMPLETED, 12/14/61

613470

LIBERAL ELECTRIC LOG TOPS

2917 KB

Kirder 2560 (+357) ϕ 3,791 MCF
TD 2600