

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK • WICHITA, KANSAS

COMPANY THE SHALLOW WATER REFINING CO.

SEC. 34 T. 21 N. 34W

FARM Gobleman "A"

NO. 8

LOG. CSW/4 NE/4

TOTAL DEPTH 4730'

COMM. 12-8-50

COMP. 12-31-50


SHOT OR TREATED

CONTRACTOR Pabco Drilling, Inc.

ISSUED 3-3-51

COUNTY Finney

KANSAS



CASING

8 5/8" 277' cem. w/150 sx
5 1/2" 4683' cem. w/125 sx

ELEVATION 2952

PRODUCTION Dry

FIGURES INDICATE BOTTOM OF FORMATIONS.

surface clay & sand	40
sand, shale & shells	95
sand	115
shale & shells	175
shale	540
sand	560
shale & sand	650
shale & shells	1115
sand	1160
shale & shells	1440
anhydrite	1555
shale & shells	1800
shale & salt	1985
shale & red bed	2025
anhydrite	2050
shale & shells	2215
shale & lime	2355
lime	3238
shale & lime	3328
lime	3714
lime & shale	3790
lime	3830
lime & shale	4181
lime	4219
lime & shale	4418
shale & lime	4616
shale	4625
shale & lime	4638
lime	4669
lime	4730
Total Depth	

We have Core Record

17 in.

4629-4730

Tops:

Herrington	2502
Winfield	2560
Towanda	2618
Ft. Riley	2649
Base Florence	2736
Wreford	2793
Neva	2968
Foraker	3048
Advance	3086
Pennsylvanian	3220
Tarkio	3320
Emporia	3359
Topeka	3500
Heebner	3751
Lansing-Kansas City	3769
Marmaton	4251
Mississippian	4629
Mississippi Lime	4633