

WILDCAT

4-190W MAP NO. K-51SEC. 4-21S-34WTATE Kans COUNTY FinneyLOC. C SW NEOPER. Aikman Brothers - Amarillo, Texas

FT/FR _____ LINE

WELL 1 FARM Frank Baker

FT/FR _____ LINE

WC

ELEV. 2992 GR. 2994 DF 2997 KSStrata Drlg. GEOL. Paul Buckthall.R. 4-6-65 SPUD 3-29-65 COMP. 4-22-65FD 4969 FM. Miss PBD. _____D&A

WC-2 mi N of Nunn Field (LKc-Marm-Chero & Miss Oil)

8 5/8" @370 w/325 sx.

Data Inc.

(KB Log)

Winf 2647 / 350

CG 2875 / 122

Hb 3832 - 835

Lans 3933 - 936

Marm 4371 -1374

Mrw 4702 -1705

Miss 4770 -1773

LTD 4969 -1972

DST #1 (Kri) 2605-30, Op 90", FB, R 25'

Sli WM, ISIP 166#/30", IFP 21#, FFP 46#,

FSIP 426#/30"

DST #2 (Lans) 4140-75 (Str Pkr), Op 90"

(5" pre flo), WB, R 220' MW, 30,000 PPM

Clor, ISIP 1167#/30", IFP 62#, FFP 145#,

FSIP 946#/30"

DST #3 (Marm) 4452-80 (Str Pkr), Op 30",WB/5", R 15' M w/NSO, ISIP 1177#/30", IFP37#, FFP 37#, FSIP 1114#/30" (Triple SMud Logger on well) , RTD 4970, Ran Log, D&A (4-14-65) COMPLETED

LIBERAL ELECTRIC LOG TOPS

2997 KB

Winfield 2646 (+351) tst XWCM
Heebner 3834 (-837)
Toronto 3848 (-851)
Lansing 3876 (-879)
Marmaton 4372 (-1375) tst Mud
Morrow 4702 (-1705)
Mississippian 4772 (-1775)
TD 4969 D & A