


7-182 W + K-51
 MAP NO. SEC. 33 TWP. 21S RGE. 34W
 STATE Kansas COUNTY Finney LOC. C SE NE
 OPERATOR Amarillo Oil Co. FT. FROM LINE
 WELL NO. 1 FARM NAME C. F. Wright FT. FROM LINE
 D. Nunn, Ext ELEV. 2961 GR 2966 DF 2968 E KB
 FR. 5/10/62 SPUD 6/4/62 COMP. 7/24/62
 CONT. Garvey Drlg. Rig #12 /GEOL.

NAME PRODUCING INTERVAL COMPLETION RECORD FROM - TO PERF. W/HOLES TREATMENT RECORD

a
 b
 c
 d



d I. P. OIL/DIST. WTR. GAS M.C.F.P.D. CHK. HRS.
 b " " " " " "
 c " " " " " "
 d

D & A

D & A ()

SIP# FI TP # FI CP# SIBHP

GOR. GR. PBD TD 4860

SIZE DEPTH CASING - CEMENT RECORD SIZE DEPTH W/SAX.

8 5/8" @ 402 275

4 1/2" @ 4439 120

OPERATOR Amarillo Oil Co. WELL NO. 1 C. F. Wright ELEV. 2968 EKB

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
KB Tops & Datums			Huber - Interest		
RTD(St Lou)	4860	-1892	Lans	3830	- 862
			BKC	4271	-1303
			Marm	4304	-1335
			Morr sh	4639	-1671
			St. Gen	4725	-1757
			St. Lou	4750	-1782
			LTD	N.A.	

DST #1 (Marm) 4285-4380, Op 15", Fr to Gd blo, SI/45",
 Op 60" fr to gd blo, R 780' mdy salt CO w/wtr spks,
 IBHP 1180#/43", IFP 175#, FFP 430#, FBHP 1150#/45".
 RTD 4860. Log.

WLT #1 (Marm) Op 1 hr., R 9800 cc wtr(95% filtrate)
 ISIP 1000#/3", FP less than 50#, FSIP 1000#/3".

WLT #2 (Lans) 4112-14 1/2, Op 50", R 20,600 cc filt wtr,
 ISIP 1100#/1 1/2", IFP 0#, FFP 1115#, FBHP 1115#/NT.

WLT #3(Marm) 4307 1/2-10, no rec, no press.

WLT #4 (Lans) 4112-14 1/2, pkr failed, no rec, no press.

WLT #5(Lans) 4106-08, Op 40", R 20,600 cc filt wtr, w/NS,
 ISIP 1190#/5", IFP 0#, FFP 1190#, FSIP 1190#/NT.

4½" @ 4439/120 sx. CO 4406 PBDT, MICT, pf 24/4324-30
(Marm) no test nat, A/500, 15%, swb dry w/SXW, SI
12 hours, FU 1300' wtr in hole w/scum oil, frac
5,000 gal Gell acid x 5000# sd, flush B treated wtr/30 min
SIP 200#, swb 274 BLW w/SSO/NT, swb 34 BF, est 9% oil/
8 hrs., SQ 4324-30 w/115 sx. 20/4307-12 (Marm) A/500 (15%),
swb ld, rec 109 BL no sho, SI 12 hours, swb 8 B Brackish
wtr w/no sho, D & A. 7/11/62.

Was WC (3½ miles N of Miss Oil in Sonderegger Pool)
Is Pool Well - Nunn, Ext.

LIBERAL ELCTRIC LOG TOPS

2968 KB

Winfield 2575 (+393)
Heebner 3784 (-816)
Lansing 3830 (-862)
Marmaton 4300 (-1332) swb XW w/SSO
Morrow 4639 (-1671)
Miss 4724 (-1756)
TD 4860 D & A