

# KANSAS DRILLERS LOG

API No. 15 — 093 — 20698  
County Number

Operator

Coastal Oil & Gas Corporation

Address

Post Office Box 1332, Amarillo, Texas 79189

Well No.

3

Lease Name

Miller

Footage Location

1980 feet from ~~SEC~~ (S) line 660 feet from (E) ~~TRQ~~ line

Principal Contractor

DNB Drilling Co.

Geologist

Louis Heyman

Spud Date

8-22-80

Total Depth

4952

P.B.T.D.

4901

Date Completed Perforated 9-9-80

Drilled: 8-31-80

Oil Purchaser

Derby


S. 15 T. 215 R. 35 W

Loc. C-NE-SE

County Kearny

640 Acres

N



Locate well correctly

Elev.: Gr. 3054

DF KB

## CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8 5/8	24	552	Class 'H'	100	3% Ca Cl
					Poz	275	6% Gel, 2% CaCl
Production	7 7/8	5 1/2	14	4940	Poz	170	2% Gel, 18% Salt
							12.5#/sk Kaolite

## LINER RECORD

## PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			4	4"	4832-36
TUBING RECORD					
Size	Setting depth	Packer set at			
2 3/8	4775				

## ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Acid: 1,000 gals 15% HCL with additives.	

## INITIAL PRODUCTION


Date of first production 9-12-80		Producing method (flowing, pumping, gas lift, etc.) Pump			
RATE OF PRODUCTION PER 24 HOURS	Oil 15 bbls.	Gas N/A MCF	Water 1 bbls.	Gas-oil ratio N/A CFPB	
Disposition of gas (vented, used on lease or sold) N/A			Producing interval(s) 4832-36		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. 3	Lease Name Miller	Oil
S <u>13</u> T <u>21</u> R <u>35</u> <sup>NE</sup> <sub>W</sub>		

WELL LOG		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.		
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.				
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Krider	2646'		Ran: DIL/SFL, CNL/FDC/GR	
Council Grove	2928'			
Lansing	3931'			
Marmaton	4442'			
Morrow Shale	4788'			
Morrow Sand	4832'			
Mississippian	4844'			
Total Depth	4952'			

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received		W. E. Rawlings
	Signature	
	Senior Engineer	
	Title	
	November 12, 1980	
	Date	