


90220 ✓

WILDCAT

1-110W Map No. B-51

OPR SHALLOW WATER REFG. CO. - Wichita,
Ks.

WELL #1 JOHNSON



S-T-R 19-21S-35W

SPOT C SE SE

CO KEARNY (Ks)

ELEV 3197 KB

TR Leben Drlg. Inc.

KB Log:

WC Discovery of Beymer NW Field

Carlile

LP P 128 BOPD (Gr 36.6°) -NW, Mar 4608-10

sh	140/3057
GH	351/2846
Graneros	450/2747
Dak	560/2637
Kiowa	818/2379
Cheyenne	890/2307
Perm	1014/2183
Bla Anh	1402/1795
Glor?	1678/1519
Cim	2141/1056
Well	2497/ 700
Holl	2660/ 537
Herr	2694/ 503
WinE	2740/ 457
FR	2806/ 391
CG	2904/ 293
Lan	3962 - 765

DST #1 (Mar) 4564-4610, Op 1 hr, GTS/40", R 1964' FO
(Gr 36°) + 600' HGCMO, ISIP 1249#/45", FPs 331-554#;
FSIP 1260#/45"

DST #2 (Mar) 4616-92, Op 1 hr, R 5'M, ISIP 83#/30",
FPs 8-8#, FSIP 33#/30"

RTD 5180' - Log - 5 1/2" @4940' w/100sx / DU tool @4654'
w/200 sx (11-5-65)

MICT, GRN Log to 4650', Top cem 3356', 1 @ 4609
(Mar), GTS/3-5", FU 1500' oil/1 hr, 7/4608-10(Mar)
FU 2200' oil/NT, FU 2600' oil/1 1/2 hrs, § 105 BO/NW/24
hrs, FU 3400' oil/NW/12 hrs - Tbg @ 4646' POP
State Pot: P 128 BOPD (Gr 36.6°) NW, Mar 4608-10
COMPLETED (Discovery of Beymer Northwest Field)

Con't

Mar 4486	4427-1230
Beymer zn	4578-1381
Johnson zn	4601-1404
Cher 4638	4635-1438
Atoka	4804-1607
Mrw	4846-1649
Ste G	4882-1685
St L	4928-1731
LTD	5180-1983
RTD	5180-1983
Spls (KB)	
B/SC	2231/ 966
Herr	2656
Mar	4581-1391
Mrw	4850
Ste G	4882
St L	4920
RTD	5180

Data Inc 3197 KB
Revised Side City Logs
 C SC TOPS
 Win 2748 + 349
 Hb ~~3940 - 743~~ 3936
~~3820 - 628~~
 Top 3980 - 763
 Lms 3992 - 795
 Mvm ~~4390 - 1193~~ 4486 - 1289
 Logged to 4650 - 5180
 Mo 4852 - 1655
 of Gen 4928 - 1731
 St L 4994 - 1797

MISC DATA
 GEOL R.W. Lange
 FTG _____
 SUPPT Phillips Petr. Co. - Support
 CSG 8" @399 w/300 sx. 5 1/2" @4940 w/100 sx.

ELEV 3194 DF SPUD DATE 10-25-65
3192 GR DRLG COMP _____
 FR by DATA 10-15-65
 COMP by 1-13-66