


90045

6-244 W MAP NO. 51 SEC. 28-21S-35W
 STATE Kansas COUNTY Kearny LOC C NE SE
 OPER. Pan American Pet. Corp., Liberal, Ks. FT/FR _____ LINE _____
 WELL #1 FARM C. E. Beymer FT/FR _____ LINE _____
 COL Wildcat * ELEV. 3101 GR. 3108 DF 3111 KB
 CONT. Big Chief Drlg. Tools GEOL. Bob Barnhart
 CO. INT. _____
 F.R. 5/4/64 SPUD 6/3/64 COMP. 6/23/64
 TD 5100 FM St Louis PBTD _____
 8" @ 2197 w/1350 sx.
 * 6 miles northwest of Amazon Ditch (Miss & Tor oil)
 3 miles south of Campbell Abdn D & A *Data Inc.*



KB Log Tops:

Chase	2622	+ 489	De Mo	4408	-1297	St L	4896	-1785
CG	2928	+ 183	Mrw fm	4766	-1655	LTD	5099	-1988
Hb	2822	- 711	Mrw sd	not called				
Missourian			Ste G	4826	-1715			
	3922	- 811						

WLT #1 (Mo) 4174-76½, Op 2 hrs, R 44,000 cc wtr, no free gas,
 1.09 cu ft. shot gas, Water res. -.278 @ 100 deg., ISIP 1300#
 /15", SP 0# - 675#, FSIP 1275#/10"

WLT #2 (De Mo) 4512-14½, Op 70", R 1800 cc wtr, NSO/G, ISIP 1250#

(~~104 BOPD NO wtr~~)

/20", SP not reported, FSIP 1250#/50"

WLT #3 (De Mo.) 4422-24½, Op 55", R 44,000 wtr NSO/G, ISIP 1300#
 /5", SP, not reported, FSIP 1300#/5"

RTD 5100 (St L) Log, D&A (6/17/64) COMPLETE

Log - Hold for work over - Data sheet.

AMARILLO ELECTRIC LOG TOPS

3111 KB

Heebner 3872 (-761)

Lansing 3931 (-820) WLT/Filt Wtr

Marmaton 4407 (-1296) WLT/Wtr

Morrow 4781 (-1670)

Ste. Gen 4826 (-1715)

St. Louis 4896 (-1785)

TD 5100 D & A