

5-97W

MAP NO.

OWWO

WILDCAT

SEC.

28-21S-35W

STATE Kans COUNTY Kearny

LOC. C NE SE

OPER. The Shallow Water Refg Co. - KC, Missouri

FT/FR LINE

WELL 1 FARM Beymer

FT/FR LINE

Geol WC in Hugoton-Beymer Disc. 3101 GR. 3108 DF 3111 KB

Leben Drlg. GEOL. BOB LANGE

CONT.

CO.

NT.

F.R.

TD.

COMP.

RECORD

8"

(KB Log)

Chase

CG

Hb

Mo

De M

Nr w fm

Mr w sd

not called

Ste G

L

LTD

5100

FM.

St L

PBT.D.

Des M

4512-14

8

natural

State Pot: P 104 BOPD-NW, Gr 32.5 deg.

8" @2197 w/1350 sx.

5 1/2" @5026 w/250 sx.

OLD INFO: (Was Pan American #1 C.E. Beyner)

WLT #1 (Mo)

4174-76 1/2, Op 2 hrs, R 44,000

cc wtr, no free gas, 1.09 cu ft shot gas,

Water res - .278 @100 deg., ISIP 1300#/#

15", SP 0# & 675#, FSIP 1275#/10"

WLT #2 (Des M)

4512-14 1/2, Op 70", R 1800

cc wtr, NSO/G, ISIP 1250#/20", SP not

reported, FSIP 1250#/50"

WLT #3 (Des M)

4422-24 1/2, Op 55", R 44,000

cc wtr, NSO/G, ISIP 1300#/5", SP not

reported, FSIP 1300#/5", RTD 5100 (St L), Log, D&A (6-17-64)

NEW INFO: MIRT 3-11-65, CO 5099 OTD, 5 1/2" @5026 w/250 sx., DV too

@4600, Ran Corr log, CO 5100, 50A in OH 5026-5100, NS, 500A, \$

2 3/4 BFPH w/scum oil, 1000A, \$ 1d, \$ 2 BWPH w/scum oil,

Plg @5005, Pf 20/4978-83 (St L), 1 BA, \$ 1d, \$ 1/2 BSWPH/

3 hrs, Plg @4950, Pf 20/4925-30, P (St L), \$ dry, 1 BA, \$ dry,

1000A, Rec 1d, \$ 5 BWPH w/scum oil, PB 4860, Pf 20/4830-


35 (Ste G), SO & Gas - nat, 1000A, \$ 1d, \$ 5 BWPH w/scum oil &

SG, PB 4530, 1d hole w/200' wtr, Pf 8/4512-14 (Des M), \$ 5 BO &

1d wtr/20", \$ 5 BO-NW/20", P 80 BOPD-NW, P 84 BOPD-NW, Gr 32.5

deg., State Pot: P 104 BOPD-NW, Gr 32.5 deg., Des M 4512-14 -

COMPLETED



Data Inc.