

State Geological Survey
KANSAS DRILLERS LOG


IMPORTANT
Kans. Geo. Survey request
samples on this well.
CONFIDENTIAL

15-093-2026

API No. 15 —————
County Number

S. 22 T. 21S R. 36W
Loc. NW/4
County KEARNY

640 Acres
N



Locate well correctly
Elev.: Gr. 3231

DF KB

Operator
Stoltz, Wagner & Brown

Address
Box 1714 Midland, Texas 79701

Well No. #1 Lease Name ADAMSON

Footage Location
1250 feet from (N) line 1250 feet from (W) line

Principal Contractor
Service Drilling Company

Geologist

Spud Date 3/5/76 Total Depth 3105 P.B.T.D. 3058

Date Completed 3/18/76 Oil Purchaser NA

CASING RECORD

K. G. S. LIBRARY

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4	8-5/8	20#	315	lite	250	3% CC
Production	7-7/8"	4-1/2	9-1/2	3103	50/50 poz	180	2% gel, 37% salt

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Socks cement	Shots per ft.	Size & type	Depth interval
			13 holes	DP jet 3/8"	2971-3027
			60 holes	DP jet	3030-2970

Size	Setting depth	Packer set at
2-3/8"	3032'	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Acidized w/2000 gals 15% HCL, Fraced w/150 bbls gel wtr & 55,000# 20/40 sand	2971-3027
Acidized w/1500 gals 15% HCL acid & Fraced w/120,000 gals fresh water, 100,000# River Sand	3030-2970

Ran Dual Laterolog & Formation Density Log

Ran Cement Bond Log & Collar Log.

Chase 2690
Winfield 2762
Council Grove 2956

STOLTZ, WAGNER & BROWN
P.O. BOX 1714, MIDLAND, TX. #1 ADAMSON 22-21-36W 100'NW, C NW

NTR SERVICE DRLG. CO. CTV KEARNY

FIELD WC (20-3/4 N OF PANOMA)

3231 GL CM 3/6/76 CARD ISSUED 7/7/77 IP TEMP ABD CO GR

LOG	TOPS	DEPTH	DATUM
CO GR		2976	+ 255
TD		3105	+ 126

8-5/8" 315/250sx, 4 1/2" 3103/180sx
MICT - PF 2971-3027 OA, AC 2000, TEMP ABD