

KANSAS DRILLERS LOG

API No. 15 — 075 — KCC WICHITA
 County Number

S. 32 T. 21S R. 41 E
W

Loc. C SW NE
 County Hamilton

Operator

Tadd Petroleum Corporation

Address

830 Denver Club Bldg., Denver, CO 80202

Well No.

3211-B

Lease Name

HCU

Footage Location

1980 feet from (N) (S) line

1980

feet from (E) (W) line

Principal Contractor

Service Drilling Co.

Geologist

None

Spud Date

6/7/79

Total Depth

2871


P.B.T.D.

2849

Date Completed

8/21/79

Oil Purchaser

640 Acres
N

Locate well correctly

3667

Elev.: Gr. _____

DF _____ KB _____

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
surface	12 $\frac{1}{4}$	8-5/8"	28	232	Class H	175	3% CaCl
production	7-7/8	4 $\frac{1}{2}$ "	10.5	2870	Class H	400	4% gel
					50/50 Poz	150	2% gel

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
---	---	---	2	$\frac{1}{2}$ jet,	2766-2772
Size	Setting depth	Packer set at			
2-3/8"		2712			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
500 gal 15% HCl acid & 1000 gal 15%-70% retarded + 150# benzoic	2766-2772
17,000 gal 3% gelled acid + 12,000# 20-40 sand @ 50% CO ₂	2766-2772

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)				
not yet connected for sales	pumping				
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	CFPB
	---	45 bbls.	50 MCF	---	
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		
to be sold			2766-2772		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 383rd So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Driller's name will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

erator

Ladd Petroleum Corporation

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

SEP 26 2001

ORIGINAL

Well No.

3211-B

Lease Name

HCU

gas

KCC WICHITA

S 32 T 21SR 41 E

W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.

TOP

BOTTOM

NAME

DEPTH

Winfield

2740

Logs run

GR/N

2849-1000

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Signature

Title

Date

6-30-80