

12-106W

MAP NO.

50

SEC. 12-21S-41W

STATE Kans COUNTY Hamilton

LOC. C NE SW

OPER Texaco Inc. - Wichita, Kansas

FT/FR

LINE

WELL 1 FARM A.L. Bengston Unit

FT/FR

LINE

POOL Bradshaw

ELEV. 3601

GR. 3606

DF 3609

KB

LOC. INT. Wakefield Drlg.

GEOL.

INT. 2850' Gas Test

F.R. 11-5-63

SPUD 11-7-63

COMP. 12-10-63

TD 2812

FM. Winfield

PBD. 2800

Completion Record

PRODUCING FM.

FROM

TO

PERF W/HOLES

TREATMENT

Winfield

2782-92

20

Frac

I.P. COF 340,000 Cfgpd, SICP 450#

Casing Record

7" @250 w/150 sx.

4½" @2812 w/50 sx.

Data Inc.

(KB Log)

CSO Win 2766 + 843

Chase 2720 + 889 LTD 2812 + 797

Winf 2769 + 840 RTD 2814 + 795

Por 2779 + 830

B/Por 2803 + 806

RTD 2814, Log, 4½" @2812 w/
50 sx + 90 sx thru DV tool

@1065, MICT, CO 2800 PBD, Winf 20/2782-92, \$ dry w/sho gas/

3 hrs, Frac 10,000# sd x 15,000A, \$ on ld, \$ & flo 158 BL & SW + 606,000 Cfgpd/NT, Flo 9 BSW, 606,000 Cfgpd/8 hrs, \$ 76 BLW + 6 BSW/10 hrs, Gas TSTM, \$ 4 BSW & Ga 150,000 Cfgpd, \$ 6 BSW/12 hrs, Ga 200,000 Cfgpd, FU 5 BSW/12 hrs, Ga 150,000 Cfgpd/12 hrs, SIP 400#, FU 5 BSW/12 hrs, Ga 200,000 Cfgpd, \$ & Flo 5 BSW/10 hrs, Ga 310,000 Cfgpd to 340,000 Cfgpd on 11-24-63 + 6 BSW/11 hrs, Ga 340,000 to 350,000 Cfgpd on 11-25-63 + 4½ BSW/10 hrs, 46 hr SIP 435#, OF test 310,000 Cfgpd - dry 11-28-63, 46 hr SIP 430#, OF test 325,000 Cfgpd - dry, Cal OF 340,000 dry, SICP 450#/48 hrs, Winf 2782-92 - COMPLETED (12-1-63)