

9-186W

REPL. COMP.

SEC. 15-21S-41W

MAP NO. _____

STATE Kans. COUNTY HamiltonLOC. C SW NEOPER. Livingston Oil Co., Tulsa, Okla.

FT./FR. _____ LINE _____

WELL #1-15 FARM F. J. Gillan

FT./FR. _____ LINE _____

BRADSHAW FIELD


ELEV. 3630 GR. 3634DF 3636 KB _____

EARL F. WAKEFIELD DRLG. TOOLS

CO. _____ GEOL. _____

F.R. 10/2/61 SPUD 10/4/61 COMP. 9/18/62TD 2778 FM. Win PBTD _____

PRODUCING FM.	FROM	TO	PERF W/HOLES	TREATMENT
Win	2763	- 78	OH	Nat
I.P. Ga 4,900,000 Cfgpd, SIP 450#				

*Data Inc.*

NOTE: This was originally drilled & operated by Hamilton Bros.
Information released 3/1/64

KB Spl Tops:

Win 2760 + 876

Poro(est) 2766 + 870

RTD 2778 + 858

No surf pipe set, No DST's of Cores
Drill to 2763 & set 4½" @ 2763 w/460
sx (cem to surf) DD w/ 3-7/8" bit,
GTS/immed. @ 2766, RTD 2778,
Ga 450,000 Cfgpd, No logs run,

Released rotary 10/9/61, Ga 463,000 Cfgpd thru 2" orifice w/no
back pressure, Ga 290,000 Cfgpd thru 2" orifice w/250# back pressure,
FCP 225#, Ga 267,000 Cfgpd, FCP 270#, Delivered 263,000
Cfgpd/24 hrs, CP 290#, BTU 860, No treatment,
State Ind. OF (2/18/64) 4,900,000 Cfgpd, SIP 450#,

Win OH 2763-78 COMPLETE

REPLACEMENT COMPLETION (4/28/64) For additional information