

10-254W 50 ✓
MAP NO.

SEC. 5 TWP. 21S RGE. 41W

STATE Kansas COUNTY Hamilton LOC. NW NW SE

OPERATOR Champlin Oil & Refg. Co. FT. FROM LINE

WELL NO. 1 FARM NAME Kuykendall Gas Unit FT. FROM LINE

Bradshaw ELEV. 3664 GR 3669 E DF 3677 E K.B.

FR. 8/15/62 SPUD 8/19/62 COMP. 10/23/62

CONT. Eark Wakefield Rotary /GEOL.

NAME PRODUCING INTERVAL	COMPLETION RECORD FROM - TO	PERF. W/HOLES	TREATMENT RECORD
a			
b			
c			
d			

a I. P. OIL/DIST. WTR. GAS M.C.F.P.D. CHK. HRS.

b " " " " " "

c " " " " " "

d

D & A

D & A ()

SIP# FI TP # FI CP# SIBHP

GOR. GR. PBD. TD 2875

SIZE	DEPTH	CASING - CEMENT W/SAX.	RECORD SIZE	DEPTH	W/SAX.
7 5/8" @	212	150			
4 1/2" @	2874	100			

OPERATOR Champlin Oil & Refg. WELL NO. 1 Kuykendall Gas U. ELEV. 3669 EDE

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
2900' Tst (Gas)			DF Tops & Datums		
Anh	2363		Anh	2360	+1309
B/Anh	2383		B/Anh	2382	+1287
Herr	2698		Herr	2696	+ 973
Kri	2733		Kri	2729	+ 940
Winf	2770		Winf	2770	+ 899
RTD (Perm)	2875	+ 794	LTD	2873	+ 796

RTD 2875. Log. 4 1/2" @ 2874 w/100 sx, MICT. 16/2858-62 & 16/2836-40 & 16/2816-20 (Winf) 500 A, lost 7 BAW, NSG, BP @ 2810. 8/2794-96 & 16/2782-86 (Winf) Cem thru perfs 2782-96 w/100 sx, CO 2810. Re-Perf 4/2794-96 & 8/2782-86 (Winf) 500 A, sli blo gas, Frac (12,000 A x 1700# sd x 400# walnut shells), sli SG - löt, part ld, Swb 60 BSW/12 hrs., 12 hour SIP 40#, Flu level 1800' from surf., (water) D & A 9/8/62.

NOTE: Information released 10/12/62. 902
 CSPet EL-log Winf 2770 + COMPLETED