

MAP NO. \_\_\_\_\_ ELEV. 2905KB, 2902DF  
 STATE Kansas COUNTY Finney SEC. 5 Twp 21S Rge 31W  
 OPERATOR Pet-Ex Company LOC. C NE NE  
 WELL NO. 1 FARM NAME Breyfogle FT. FROM \_\_\_\_\_ LINE  
 COL Wildcat FT. FROM \_\_\_\_\_ LINE  
 FR. 2-7-61 SPUD 2-6-61 COMP. 2-19-61  
 CONT./GEOL. Red Tiger Rig #1

**COMPLETION RECORD**

NAME PRODUCING INTERVAL	FROM - TO	PERF. W/HOLES	TREATMENT RECORD
a			
b			
c			
d			

a I. P. OIL/DIST. \_\_\_\_\_ WTR. \_\_\_\_\_ GAS \_\_\_\_\_ M.C.F.P.D. \_\_\_\_\_ CHK. \_\_\_\_\_ HRS. \_\_\_\_\_  
 b " " " " " " " " " "  
 c " " " " " " " " " "  
 d \_\_\_\_\_


D & A D & A (X)

SIP# \_\_\_\_\_ FI TP # \_\_\_\_\_ FI CP# \_\_\_\_\_ SIBHP \_\_\_\_\_  
 GOR. \_\_\_\_\_ GR. \_\_\_\_\_ PBDT \_\_\_\_\_ TD 4820  
**CASING - CEMENT RECORD**  
 SIZE DEPTH W/SAX. SIZE DEPTH W/SAX.  
8 5/8" 279 210 \_\_\_\_\_ \_\_\_\_\_ \_\_\_\_\_

OPERATOR Pet-Ex Company WELL NO. #1 Breyfogle ELEV. 2902 DF

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
Heebner	3934		Anhydrite	2103	
Toronto	3953		Base Anhydrite	2170	
Lansing	3983		Herrington	2685	
			Krider	2715	
			Winfield	2766	
			Ft. Riley	2877	
			Heebner	3936	
			Toronto	3955	
			Lansing	3983	
			Base Kansas City	4400	
			Marmaton	4418	
			Cherokee	4544	
			Mississippian	4660	

Pure F/O; Kerr-McGee & Sunray-DHM, Coop-Ac.

Used gas sniffer unit.

Spud 2-6-61, 8 5/8" @ 279 w/210 sx.

Zone 4613-81, had show oil in samples.

DST #1 (Cherokee-Mississippian) 4613-81, op 30 mins, Rc 60' mud/NS, ISIP 560/30 mins, FP 0-0, FSIP 425/30 mins.

RTD4820, logs to 4820. D&A 2-19-61.

COMPLETE.

LIBERAL ELECTRIC LOG TOPS

2905 KB

Winfield 2766 (+139)  
Heebner 3938 (-1033)  
Lansing 3983 (-1078)  
Marmaton 4418 (-1513)  
St. Gen 4660 (-1755) tst, NS  
RTD 4820